Shade Tree Commission of Radnor Township Wayne, Pennsylvania

AGENDA

Wednesday February 24, 2016 6:30 PM

Pledge of Allegiance

209 Matsonford Road GP # 16-13 Archbishop Carroll High School

Baseball and Lacrosse Fields 9,300 CY of dirt (keep on site)

131/133 Garrett Avenue 2015-S-03

Subdivide property into two

Construct 2 new single family dwellings

Clem Macrone Park C # 16-01

810 Conestoga Road Remove 30 trees

Alterations and renovations to park

Radnor Memorial Library C # 16-02

114 W. Wayne Ave. Remove 5 trees

Renovations and expansion

Tree Removals
Not approved for removal

836 Milmar Road 14 trees were removed (6) of which were heritage Numerous ground stumps observed as well

Hazardous Tree Removals Approved for removal by Township Arborist

Radnor Station Office Building

Applicant was asked to plant a tree

40" Ash


Tree has declined and is dead

Hazard to parking lot and next to building

ARCHBI SHOP CARROLL HI GH SCHOOL


2016 ATHLETIC FIELD RENOVATIONS





DRAWING SCHEDULE

- 1. COVER SHEET
- 2. EXISTING FEATURES, DEMOLITION & SOIL, VEGETATION & WATER RESOURCES PLAN
- 3. PROPOSED SITE & POST CONSTRUCTION STORMWATER MANAGEMENT SITE PLAN BASEBALL FIELD
- 4. PROPOSED SITE & POST CONSTRUCTION STORMWATER MANAGEMENT SITE PLAN LACROSSE AND FIELD HOCKEY
- 5. POST CONSTRUCTION STORMWATER MANAGEMENT & GENERAL CONSTRUCTION DETAILS
- 6. EROSION & SEDIMENTATION CONTROL PLAN
- 7. EROSION & SEDIMENTATION CONTROL DETAILS



P.O. BOX 1992

SOUTHEASTERN, PA 19399

F: 610-240-0451 E:INFO@SITE-ENGINEERS.COM

NPDES PERMIT APPLICATION

PLAN PREPARED FOR:

ARCHBISHOP CARROLL

211 MATSONFORD ROAD


WAYNE, PA 19087


OVERALL PROPOSED SITE

SHEET 1 of 7 PLAN

SCALE: 1"=100'

PENNSYLVANIA DATE: 28 JANUARY 20





GENERAL NOTES

- 1. BASEBALL FIELD REFERENCE PLAN: "PLAN OF TOPOGRAPHIC SURVEY, BASEBALL FIELD AT ARCHBISHOP CARROLL HIGH SCHOOL" PREPARED BY E.B. WALSH AND ASSOCIATES, INC. DATED
- 2. LACROSSE FIELD SHOWN IN ACCORDANCE WITH ACTUAL FIELD INSTRUMENT SURVEY CONDUCTED UPON THE GROUNDS ON AUGUST 2015 BY JEFFERY P. TURNER, PLS FROM VARIOUS DEEDS AND PLANS OF RECORD; SURVEY WAS PREFORMED WITHOUT THE BENEFIT OF A TITLE REPORT; PROPERTY MAY BE SUBJECT TO CERTAIN RIGHTS OF OTHERS.
- 3. ELEVATIONS ARE BASED ON BENCHMARK PROVIDED ON REFERENCE PLAN.
- 4. EXISTING SUBSURFACE UTILITY INFORMATION INDICATED IS BASED UPON VISUAL FIELD INSPECTION BY SURVEYORS SUCH INFORMATION CONCERNING THE SIZE, LOCATION, DEPTH, QUANTITY, ETC. OF SUBSURFACE UTILITIES IS APPROXIMATE IN NATURE AND HAS BEEN OBTAINED AS A SUPPLEMENT TO THE SITE SURVEY. THE INFORMATION PROVIDED IS REPRESENTATIVE OF SUBSURFACE CONDITIONS ONLY AT LOCATIONS AND DEPTHS WHERE SUCH WAS OBTAINED. THERE IS NO EXPRESSED OR IMPLIED AGREEMENT THAT UTILITY SIZE, LOCATION, DEPTH, QUANTITY, ETC. AS SHOWN EXISTS BETWEEN EXPLORED LOCATIONS. ACCORDINGLY, UTILITY INFORMATION SHOWN SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. IT IS INCUMBENT UPON THE CONTRACTOR TO VERIFY THE SIZE, LOCATION, DEPTH, QUANTITY, ETC. OF ALL UTILITIES BEFORE EXCAVATION.

DEMOLITION NOTES

- 1. RADNOR TOWNSHIP SHALL BE NOTIFIED PRIOR TO DEMOLITION WORK TO ASCERTAIN IF ANY PERMITS ARE REQUIRED.
- 2. THIS PLAN DOES NOT SHOW ALL UTILITIES. CONTRACTOR SHALL NOTIFY UNDERGROUND UTILITY USERS AT LEAST THREE DAYS PRIOR TO CONSTRUCTION IN ACCORDANCE WITH PA ONE CALL REGULATIONS (CALL 1-800-242-1776) AND SHALL FIELD LOCATE ALL UTILITIES THAT MAY BE PRESENT IN WORK AREA. 2. IF ANY EXISTING UTILITIES CONFLICT WITH CONSTRUCTION, PLANS SHALL BE MADE WITH UTILITY COMPANY FOR RELOCATION.
- 3. CONTRACTOR SHALL FOLLOW ALL REQUIREMENTS OF THE DURING CONSTRUCTION EROSION AND SEDIMENT CONTROL PLAN, AS APPLICABLE, INCLUDING THE STABILIZED CONSTRUCTION ENTRANCE, SILT FENCE, TREE PROTECTION, AND IMMEDIATE STABILIZATION OF ANY DISTURBED AREAS.

PLAN LEGEND

BOLD LINES: FEATURES TO BE DEMOLISHED FADED LINES: FEATURES TO REMAIN ----- SUPPLEMENTAL CONTOUR (1' INTERVAL) ----- INDEX CONTOUR (5' INTERVAL) ----- ST ----- EXISTING STORM SEWER PIPING ---- G ----- EXISTING GAS MAIN ---- W ------ EXISTING WATER MAIN / SERVICE ---- E ------ EXISTING OVERHEAD UTILITY WIRES EXISTING EDGE OF WOODS EXISTING CURB LINE

NUM. DATE REVISION PLAN PREPARED BY: SITE ENGINEERING CONCEPTS, LLC

P.O. BOX 1992

SOUTHEASTERN, PA 19399 F: 610-240-0451 E:INFO@SITE-ENGINEERS.COM

NPDES PERMIT APPLICATION PLAN PREPARED FOR:


ARCHBISHOP CARROLL 211 MATSONFORD ROAD


PENNSYLVANIA

WAYNE, PA 19087 **DELAWARE COUNTY**

EXISTING FEATURES PLAN **DEMOLITION PLAN** SHEET SOIL, VEGETATION & 2 of 7 WATER RESOURCES PLAN | SCALE: 1"= 40'

RADNOR TOWNSHIP





ENGINEERING CONSTRUCTION OVERSIGHT

THE CONTRACTOR SHALL PROVIDE ENGINEERING CONSTRUCTION OVERSIGHT FOR THE PROPOSED STORMWATER BMPS. ADDITIONAL SOIL TESTING MAY BE REQUIRED PRIOR TO THE INSTALLATION OF INFILTRATION BMPS TO ENSURE PROPER LOCATION AND FUNCTION. A LICENSED PROFESSIONAL KNOWLEDGEABLE IN THE DESIGN AND CONSTRUCTION OF STORMWATER BMPS, PREFERABLY THE DESIGN ENGINEER, SHALL CONDUCT THE OVERSIGHT. OVERSIGHT IS NECESSARY FOR THE FIVE INFILTRATION

AFTER EXCAVATION OF BED, AFTER ALL PIPING IS INSTALLED BUT BEFORE PIPING IS COVERED WITH STONE/GEOTEXTILE, AND AFTER INFILTRATIOM BED IS COMPLETED. FINAL CERTIFICATION FROM THE LICENSED PROFESSIONAL THAT THE INFILTRATION BED HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLAN IS REQUIRED PRIOR TO PADEP'S ACCEPTANCE OF THE NOTICE OF TERMINATION FOR THE NPDES PERMIT.

PCSM LONG TERM OPERATIONS AND MAINTENANCE REQUIREMENTS

UNTIL THE PERMITTEE OR CO-PERMITTEE HAS RECEIVED WRITTEN APPROVAL OF A NOTICE OF TERMINATION, THE PERMITTEE OR CO-PERMITTEE WILL REMAIN RESPONSIBLE FOR COMPLIANCE WITH THE PERMIT TERMS AND CONDITIONS INCLUDING LONG-TERM OPERATION AND MAINTENANCE OF ALL PCSM BMPS ON THE PROJECT SITE AND IS RESPONSIBLE FOR VIOLATIONS OCCURRING ON THE PROJECT SITE. THE PERMITTEE OR CO-PERMITTEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOTICE OF TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS. FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITTEE OR CO-PERMITTEE SHALL RECORD AN INSTRUMENT WITH THE RECORDER OF DEEDS WHICH WILL ASSURE DISCLOSURE OF THE PCSM BMP AND THE RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST IDENTIFY THE PCSM BMP, PROVIDE FOR NECESSARY ACCESS RELATED TO LONG—TERM OPERATION AND MAINTENANCE FOR PCSM BMPS AND PROVIDE NOTICE THAT THE RESPONSIBILITY FOR LONG—TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEES, AND PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION UNDER PA CODE CHAPTER 102.7(B)(5) (RELATING TO PERMIT TERMINATION). THE PERSON RESPONSIBLE FOR PERFORMING LONG-TÈRM OPÈRATION AND MAINTENANCE MAY ÉNTER INTO AN AGREEMENT WITH ANOTHER PERSON INCLUDING A CONSERVATION DISTRICT, NONPROFIT ORGANIZATION, MUNICIPALITY, AUTHORITY, PRIVATE CORPORATION OR OTHER PERSON, TO TRANSFER THE RESPONSIBILITY FOR PCSM BMPS OR TO PERFORM LONG-TERM OPERATION AND MAINTENANCE AND PROVIDE NOTICE THEREOF TO THE DEPARTMENT. A PERMITTEE OR CO-PERMITTEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL REMAIN JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG-TERM OPERATION AND MAINTENANCE OF THE

PCSM REPORTING AND RECORDKEEPING

THE PCSM PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.

NOTICE OF TERMINATION

PCSM BMPS LOCATED ON THE PROPERTY.

UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY UNDER CH. 102.22(A)(2) (RELATING TO PERMANENT STABILIZATION), AND INSTALLATION OF BMPS IN ACCORDANCE WITH AN APPROVED PLAN PREPARED AND IMPLEMENTED IN ACCORDANCE WITH CH. 102.4 AND 102.8 (RELATING TO EROSION AND SEDIMENT CONTROL REQUIREMENTS; AND PCSM REQUIREMENTS), THE PERMITTEE OR CO-PERMITTEE SHALL SUBMIT A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION DISTRICT. THE NOTICE OF TERMINATION MUST INCLUDE: (1) THE FACILITY NAME, ADDRESS AND LOCATION.

- (2) THE OPERATOR NAME AND ADDRESS. (3) THE PERMIT NUMBER.
- (4) THE REASON FOR PERMIT TERMINATION. (5) IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS IN ACCORDANCE WITH CH. 102.8(M) AND PROOF OF COMPLIANCE WITH CH. 102.8(M)(2).

FINAL CERTIFICATION

THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL, WHICH READS AS FOLLOWS: "I (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA. C.S.A. CHAPTER 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT TH PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION PRACTICES." (1) THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM (2) THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE LONG—TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS.

AMOUNT OF STABILIZATION REQUIRED BEFORE ANY STORMWATER RUNOFF CAN ENTER ANY PCSWM BMP.

BEFORE ANY STORMWATER RUNOFF CAN ENTER ANY PCSWM BMP, ALL CONTRIBUTARY UPSLOPE DRAINAGE AREAS MUST HAVE ACHIEVED FINAL STABILIZATION. FINAL STABILIZATION IS WHEN AN AREA HAS ACHIEVED A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON—VEGETATIVE COVER (STONE/PAVING) WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS.

STORM WATER MANAGEMENT (BMP) FACILITY OWNERSHIP, **OPERATIONS, & MAINTENANCE NOTES:**

ALL STORMWATER CONVEYANCE AND MANAGEMENT FACILITIES SHOWN ON THIS PLAN ARE PERMANENT AND ARE NOT TO BE REMOVED OR FILLED. THE PROPERTY OWNER AND THEIR HEIRS, ASSIGNS OR SUCCESSORS SHALL BE RESPONSIBLE FOR THE PERPETUAL MAINTENANCE OF THE SAID FACILITIES. TOWNSHIP MAINTAINS THE RIGHT, BUT NOT THE RESPONSIBILITY, TO ENTER SAID PREMISES TO OBSERVE OR INSPECT THE FUNCTIONING OF THESE FACILITIES. IF THE PROPERTY OWNER, HIS/HER HEIRS, ASSIGNS, OR SUCCESSORS FAILS IN ANY WAY TO MAINTAIN THE SAID FACILITIES OR CAUSES THESE FACILITIES TO BE ALTERED OR REMOVED, UPON WRITTEN NOTIFICATION BY THE TOWNSHIP, THE DEFECTS SHALL PROMPTLY BE CORRECTED BY THE PROPERTY OWNER. UPON THE OWNER'S FAILURE TO CORRECT THE DEFECTS WITHIN TIME SPECIFIED BY THE TOWNSHIP, THE OWNER, HIS/HER HEIRS, ASSIGNS, OR SUCCESSORS DO HEREBY AUTHORIZE THE TOWNSHIP AND/OR THEIR CONTRACTOR TO ENTER UPON THE SAID PROPERTY AND CAUSE THE REPAIR, MAINTENANCE, AND/OR CORRECTIONS TO BE MADE. A LIEN MAY BE FILED AGAINST THE PROPERTY FOR THE COSTS OF ALL CORRECTIONS INCLUDING APPLICABLE ENGINEERING AND/OR ATTORNEY'S FEES. THE TOWNSHIP IS UNDER NO OBLIGATION TO TAKE ANY ACTION. MAINTENANCE

- 1. MAINTAINING THE GRASS ON AND AROUND STORM WATER FACILITIES TO PREVENT LARGE VEGETATION AND ROOT SYSTEMS FROM GROWING ON OR NEAR FACILITIES AND TO PREVENT THE FORMATION OF NONVEGETATED AREAS THAT COULD FLOW INTO AND CLOG THE FACILITIES. 2. KEEPING ALL DEBRIS, INCLUDING GRASS CLIPPINGS AND LEAVES CLEAR OF INLET AND OUTLET
- 3. INLET AND OUTLET STRUCTURES SHALL BE INSPECTED MONTHLY. 4. NO TREES OR SHRUBBERY MAY BE PLACED OVER THE LOCATION OF THE INFILTRATION BED.

 5. IF INFILTRATION BED DOES NOT DRAIN WITHIN 72 HOURS AFTER THE LAST STORM EVENT IT SHALL
- BE INSPECTED AND THEN FIXED OR REPLACED AS NECESSARY.

STORMWATER INFILTRATION BED NOTES

RESPONSIBILITIES SHALL INCLUDE THE FOLLOWING:

STRUCTURES AND REMOVING ANY DEBRIS.

I. SCARIFY BOTTOM AND SIDES OF BASIN, TAKING CARE NOT TO COMPACT SOIL. 2. PERFORATED PIPE MUST HAVE PERFORATIONS NO LESS THAN 5/16" DIAMETER AND PROVIDE AN OPEN AREA OF NOT LESS THAN 3.31 SQUARE INCHES PER SQUARE FOÓT OF PIPE SURFACE. 3. ENTIRE BED, SIDES TOP AND BOTTOM, SHALL BE WRAPPED IN SYNTHETIC INDUSTRIES NON-WOVEN #1201 OR ENGINEER APPROVED EQUAL. PROVIDE A MINIMUM 1' OVERLAP AT ALL SEAMS AND JOINTS. WHERE PROTRUSIONS OR PENETRATIONS OCCUR, GEOTEXTILE SHALL BE PERMANENTLY AFFIXED TO OBJECT.
4. CARE SHOULD BE TAKEN IN THE PLACING OF STONE ATOP THE GEOTEXTILE SO AS TO AVOID TEARING OR RIPPING OF THE FABRIC. STONE SHOULD NOT BE DUMPED UNTIL A 6" LAYER OF STONE IS IN PLACE.
5. ALL INLETS AND DRAIN BASINS THAT DRAIN DIRECTLY TO INFILTRATION BEDS SHALL HAVE SNOUT OIL
AND DEBRIS FILTERS ATTACHED TO THE PIPE ENTERING THE INFILTRATION BED.

INFILTRATION BED CONSTRUCTION SEQUENCE

STAGE 1. BEFORE SITE DISTURBANCE TAKES PLACE, INSTALL CONSTRUCTION FENCING AROUND INFILTRATION BED TO PROTECT IT FROM CONSTRUCTION TRAFFIC AND STAGE 2. INSTALL SILT FENCE AS SHOWN ON PLAN.

STAGE 3. CONSTRUCT INFILTRATION BED (AND INLETS/PIPING THAT DRAINS TO THEM) AFTER ALL AREAS TRIBUTARY TO IT HAVE ACHIEVED A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER (STONE/PAVING). THEY MAY BE CONSTRUCTED EARLIER AS LONG AS IT DOES NOT RECEIVE RUNOFF FROM AREAS THAT HAVE NOT BEEN PERMANENTLY STABILIZED. INSTALL INLET PROTECTION/SILT SACKS OVER INLETS.


STAGE 4. EXCAVATE BED. EXISTING SUB-GRADE SHALL NOT BE COMPACTED OR SUBJECT TO EXCESSIVE CONSTRUCTION EQUIPMENT TRAFFIC. A LICENSED PROFESSIONAL ENGINEER OR DESIGNEE SHALL APPROVE EXCAVATED BED BEFORE CONSTRUCTION PROCEEDS. WHERE THERE IS ANY ACCUMULATION OF FINE MATERIALS OR SURFACE PONDING, THIS MATERIAL SHALL BE REMOVED WITH LIGHT EQUIPMENT AND THE UNDERLYING SOILS SCARIFIED TO A MINIMUM DEPTH OF 6 INCHES WITH A YORK RAKE (OR EQUIVALENT) AND LIGHT TRACTOR. ALL FINE GRADING SHALL BE DONE BY HAND. ALL BED BOTTOMS SHOULD


STAGE 5. GEOTEXTILE AND BED AGGREGATE SHOULD BE PLACED IMMEDIATELY AFTER APPROVAL OF SUBGRADE PREPARATION. NO SEDIMENT IS TO ENTER THE BEDS. CLEAN WASHED STONE SHALL BE USED TO CONSTRUCT BED. IF SEDIMENT ENTERS STONE, STONE SHALL BE REPLACED AND THE GEOTEXTILE FABRIC SHALL BE CLEANED OR REPLACED AS NECESSARY. INLETS SHALL ONLY COLLECT RUNOFF ONCE ALL AREAS TRIBUTARY TO THEM HAVE ACHIEVED A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER (STONE/PAVING).

STAGE 6. STONE SHALL BE PLACED IN THE BED IN MAXIMUM 8 INCH LIFTS. EACH LAYER SHALL BE LIGHTLY COMPACTED, WITH CONSTRUCTION EQUIPMENT KEPT OFF THE BED BOTTOM AS MUCH AS POSSIBLE. BEFORE PIPES ARE COVERED WITH STONE AND GEOTEXTILE, A LICENSED PROFESSIONA ENGINEER OR DESIGNEE

STAGE 7. WHEN BED IS COMPLETE, BACKFILL WITH SOIL IN MAXIMUM OF 6 INCH LIFTS, LIGHTLY COMPACT, STAGE 8. REMOVE INLET PROTECTION, SILT FENCE, AND ANY OTHER EROSION AND SEDIMENT CONTROL

MEASURES ONLY AFTER SITE IS FULLY STABILIZED AND APPROVAL IS OBTAINED FROM THE CONSERVATION





DUGOUT MANUFACTURER DETAIL


MANAGEMENT & GENERAL


CONSTRUCTION DETAILS | SCALE: NTS

PATRICK SPELLMAN, P.E.

PE-40021-E

5 of 7





NOTES:

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL MANUAL.

FABRIC WIDTH SHALL BE 30 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES.

SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE


EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE.

ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY

STANDARD CONSTRUCTION DETAIL 4-7 STANDARD SILT FENCE 18" HIGH



* POSTS SPACED AT 10 FT. MAX. USE 2-1/2 IN. DIA HEAVY DUTY GALVANIZED OR ALUMINUM POSTS.

** CHAIN LINK TO POST FASTENERS SPACED AT 14 IN. MAX. USE NO. 9 GA. ALUMINUM WIRE OR NO. 9 GALVANIZED STEEL WIRE. FABRIC TO SHAIN FASTENERS SPACED AT 24 IN. MAX. ON CENTER.

NOTES:

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL MANUAL.

FABRIC WIDTH SHALL BE 42 IN. MINIMUM.

POSTS SHALL BE INSTALLED USING A POSTHOLE DRILL.


CHAIN LINK SHALL BE GALVANIZED NO. 11.5 GA. STEEL WIRE WITH 2-1/4 IN. OPENING, NO. 11 GA. ALUMINUM COATED STEEL WIRE IN ACCORDANCE WITH ASTM-A-491, OR GALVANIZED NO. 9 GA. STEEL WIRE TOP AND BOTTOM WITH GALVANIZED NO. 11 GA. STEEL INTERMEDIATE WIRES. NO. 7 GAGE TENSION WIRE TO BE INSTALLED HORIZONTALLY THROUGH HOLES AT TOP AND BOTTOM OF CHAIN-LINK FENCE OR ATTACHED WITH HOG RINGS AT 5 FT MAX. CENTERS.

SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

STANDARD CONSTRUCTION DETAIL 4-10 SUPER SILT FENCE NOT TO SCALE



TREE PROTECTION FENCING

NOT TO SCALE

DISCHARGE HOSE—CLAMPS

PUMP—INTAKE HOSE

PLAN_VIEW

PUMP—INTAKE HOSE

CLAMPS

PUMP—INTAKE HOSE

ELEVATION_VIEW

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE

OLLOWING STANDANDS.		
PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.


NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

STANDARD CONSTRUCTION DETAIL 3-16 PUMPED WATER FILTER BAG



NOTES:


REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.


MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

STANDARD CONSTRUCTION DETAIL 3-1 ROCK CONSTRUCTION ENTRANCE



NOT TO SCALE



CHANNEL CROSS—SECTION

* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *
PDS-1		2	1.5	6	2	2	GRASS
CDSA-1		2	1.5	6	2	2	GRASS

ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES.

CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION.
SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.

NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

STANDARD CONSTRUCTION DETAIL 6-1 VEGETATED CHANNEL


NOT TO SCALE

BLANKET EDGES
STAPLED AND
OVERLAPPED

(4 IN. MIN.)

STARTING AT TOP OF
SLOPE, ROLL BLANKETS IN
DIRECTION OF WATER FLOW

INSTALL BEGINNING OF ROLL
IN 6 IN. x 6 IN. ANCHOR
TRENCH, STAPLE, BACKFILL
AND COMPACT SOIL



THE BLANKET SHOULD—
NOT BE STRETCHED;
IT MUST MAINTAIN
GOOD SOIL CONTACT

OVERLAP BLANKET ENDS 6 IN. MIN. —
WITH THE UPSLOPE BLANKED
OVERLYING THE DOWNSLOPE BLANKET
(SHINGLE STYLE). STAPLE SECURELY.

REFER TO MANUF. RECOMMENDED STAPLING PATTERN FOR STEEPNESS AND LENGTH OF SLOPE BEING BLANKETED

PREPARE SEED BED

BLANKET INSTALLATION

(INCLUDING APPLICATION OF LIME,

FERTILIZER AND SEED) PRIOR TO

NOTES:

SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.

PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.

BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.

BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

STANDARD CONSTRUCTION DETAIL 11-1

EROSION CONTROL BLANKET INSTALLATION

THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

NOT TO SCALE

EROSION AND SEDIMENTATION CONTROL NOTES

1. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION

2. AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON—SITE PRECONSTRUCTION MEETING.

3. AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.

4. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION

5. AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.

6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED

IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN.

7. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY

MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.

8. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAPS(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER.

9. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.

10. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.

11. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.

12. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING. IF THE SITE WILL HAVE EXCESS FILL THAT WILL NEED TO BE EXPORTED TO AN OFFSITE LOCATION, THE RESPONSIBILITY OF CLEAN FILL DETERMINATION AND ENVIRONMENTAL DUE DILIGENCE RESTS ON THE APPLICANT.

13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS.

14. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE

15. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION.

16. SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.

17. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS.

18. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES (6 TO 12 INCHES ON COMPACTED SOILS) PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL.

20. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES

21. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN

22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION

OF SATISFACTORY FILLS.

23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.

24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.

25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD.

26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.

27. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON—GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.

28. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.

29. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.

30. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.


31. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON.

32. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION.


33. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT—LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION.

E&S MAINTENANCE NOTES

ALL EROSION CONTROL FACILITIES, INCLUDING BUT NOT LIMITED TO THE STABILIZED CONSTRUCTION ENTRANCE, SILT FENCE, AND FILTREXX SOXX, AND INLET FILTER BAGS SHALL BE INSPECTED ON A REGULAR BASIS (AT LEAST WEEKLY) AND BEFORE AND AFTER STORM EVENTS TO ENSURE THEY ARE FUNCTIONING PROPERLY. IF THEY ARE NOT FUNCTIONING PROPERLY AND/OR HAVE BEEN KNOCKED DOWN OR OVERTOPPED, THEY SHALL BE IMMEDIATELY REPLACED. ACCUMULATED SEDIMENT SHALL BE REMOVED FROM SILT FENCE, FILTREXX SOXX, AND INLET FILTER BAGS WHEN SILT HAS ACCUMULATED TO NO HIGHER THAN 1/2 OF THE HEIGHT OF THE SILT FENCE/FILTREXX SOXX/FILTER BAG AND BE UTILIZED ON SITE.



OUTLET CROSS—SECTION



<u>UP-SLOPE FACE</u>

NOTES

A ROCK FILTER OUTLET SHALL BE INSTALLED WHERE FAILURE OF A SILT FENCE OR STRAW BALE BARRIER HAS OCCURRED DUE TO CONCENTRATED FLOW. ANCHORED COMPOST LAYER SHALL BE USED ON UPSLOPE FACE IN HQ AND EV WATERSHEDS.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.

STANDARD CONSTRUCTION DETAIL 4-6

ROCK FILTER OUTLET

NOT TO SCALE

CONSTRUCTION STAGING

CONTRACTOR MUST NOTIFY TOWNSHIP ENGINEER 48 HOURS PRIOR TO CONSTRUCTION OF TO SCHEDULE REQUIRED INSPECTIONS.

STAGE 1. INSTALL SILT FENCE, FILTREXX SOXX, AND TREE PROTECTION FENCING.

STAGE 2. INSTALL ROCK CONSTRUCTION ENTRANCES.

STAGE 3. FIELD LOCATE ALL UTILITIES AND COORDINATE WITH UTILITIES FOR

SHUTOFF/REMOVAL/RELOCATION AS NECESSARY. IMMEDIATELY STABILIZE ANY

DISTURBED AREAS.

STAGE 4. REMOVE IMPROVEMENTS AS SHOWN. IMMEDIATELY STABILIZE AREAS WITH MULCH AND SEED MIX UNLESS IMMEDIATE CONSTRUCTION TAKES PLACE ON THESE

STAGE 5. STRIP TOPSOIL AND ROUGH GRADE AREA OF PROPOSED SYNTHETIC TURF.
IMMEDIATELY STABILIZE DORMANT DISTURBED AREAS WITH THE APPROPRIATE SEED
MIXTURE. TOPSOIL STOCKPILES ARE TO BE LIMITED TO 35 FEET WITH A MAXIMUM
SIDE SLOPE OF 2:1. IMMEDIATELY STABILIZE STOCKPILE.

STAGE 6. CONSTRUCT RETAINING WALLS.

STAGE 7. CONSTRUCT SYNTHETIC TURF SUBBASE AND CONSTRUCT DRAINAGE SYSTEM.

STAGE 8. COMPLETE SYNTHETIC TURF CONSTRUCTION. FINAL GRADE AND IMMEDIATELY

STABILIZE DORMANT DISTURBED AREAS WITH THE APPROPRIATE SEED MIXTURE.


STAGE 9. ONCE SITE IS STABILIZED WITH 70% COVERAGE, CONTRACTOR MUST REMOVE EROSION AND SEDIMENTATION CONTROLS. AREAS DISTURBED DURING REMOVAL MUST BE STABILIZED IMMEDIATELY.

ANTICIPATED START OF CONSTRUCTION — SPRING 2016
ANTICIPATED COMPLETION OF CONSTRUCTION — FALL 2016

NOTE (IF NECESSARY):
THE PERMITTEE SHALL PROVIDE ENGINEERING CONSTRUCTION OVERSIGHT FOR THE PROPOSED STORMWATER BMPS. ADDITIONAL SOIL TESTING MAY BE REQUIRED PRIOR TO THE INSTALLATION OF INFILTRATION BMPS TO ENSURE PROPER LOCATION AND FUNCTION. A LICENSED PROFESSIONAL KNOWLEDGEABLE IN THE DESIGN AND CONSTRUCTION OF STORMWATER BMPS, PREFERABLY THE DESIGN ENGINEER, SHALL CONDUCT THE OVERSIGHT. OVERSIGHT IS NECESSARY FOR THE FOUR INFILTRATION

AT LEAST THREE INSPECTIONS SHALL BE CONDUCTED FOR THE INFILTRATION BED:
AFTER EXCAVATION OF BED, AFTER ALL PIPING IS INSTALLED BUT BEFORE PIPING IS
COVERED WITH STONE/GEOTEXTILE, AND AFTER INFILTRATION BED IS COMPLETED.

FINAL CERTIFICATION FROM THE LICENSED PROFESSIONAL THAT THE INFILTRATION BED
HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLAN IS REQUIRED PRIOR TO
PADEP'S ACCEPTANCE OF THE NOTICE OF TERMINATION FOR THE NPDES PERMIT.



SITE ENGINEERING CONCEPTS, LLC
P.O. BOX 1992

SOUTHEASTERN, PA 19399

P: 610-240-0450 F: 610-240-0451 E:INFO@SITE-ENGINEERS.COM

PLAN PREPARED FOR:

ARCHBISHOP CARROLL

211 MATSONFORD POAD

211 MATSONFORD ROAD WAYNE, PA 19087

O OFFILMENT

DELAWARE COUNTY

7 of 7
SCALE: NTS

SHEET

PENNSYLVANIA

DATE: 28 JANUARY 201

EROSIONS & SEDIMENT CONTROL DETAILS

RADNOR TOWNSHIP


RATHICK SPELLMAN!


ENGINEER /


No. 40021E

PATRICK SPELLMAN, P.E.

PE-40021-E







EROSION AND SEDIMENTATION CONTROL NOTES

- 1. EROSION AND SEDIMENT BMP'S MUST BE CONSTRUCTED, STABILIZED AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMP'S. 2. STORMWATER INLETS WHICH DO NOT DISCHARGE TO SEDIMENT TRAPS OR BASINS, MUST BE PROTECTED UNTIL THE TRIBUTARY AREAS ARE STABILIZED.
- 3. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE 2: 1 OR FLATTER.
- 4. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMP'S MUST BE STABILIZED IMMEDIATELY.
- 6. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS TO THE CONTROLS FOR GRADING AND ACQUIRING BORROW TO CONSTRUCT THOSE CONTROLS.
- 7. AT LEAST THREE DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INCORPORATED AT 1-800-242-1776 FOR BURIED UTILITY LOCATIONS.
- 8. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE.
- 9. THE PROJECTS RECEIVING WATERCOURSE IS MEADOWBROOK RUN WITHIN THE DARBY CREEK WATERSHED, AND THE CHAPTER 93 CLASSIFICATION IS CWF, MF.
- FILTER FABRIC FENCING & STRAW BALE BARRIERS
- FILTER FABRIC FENCING AND STRAW BALE BARRIERS MUST BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE OR BARRIER SECTION MUST EXTEND 8 FEET UP SLOPE AT 45 DEGREES TO THE ALIGNMENT OF THE MAIN FENCE OR BARRIER.
- 2. SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH ½ THE ABOVE GROUND HEIGHT OF FILTER FABRIC FENCING OR 1/3 THE ABOVE GROUND HEIGHT OF STRAW
- 3. ANY FILTER FABRIC FENCING OR STRAW BALE BARRIER WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH ROCK FILTER OUTLETS. 4. STRAW BALE BARRIERS SHOULD NOT BE USED FOR MORE THAN 3 MONTHS.
- SEDIMENT REMOVAL 1. SEDIMENT MUST BE REMOVED FROM STORM WATER INLET PROTECTION AFTER EACH RUNOFF EVENT.
- ALL SILT AND FOREIGN MATTER SHALL BE REMOVED FROM THE TOP OF AND PROPERLY DISPOSED OF BEFORE WEARING SURFACE IS INSTALLED.
- 3. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS.
- 4. SEDIMENT REMOVED FROM BMP'S SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED IN TOPSOIL STOCKPILES.
- 1. MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROL DEVICES IS THE RESPONSIBILITY OF THE OPERATOR DURING CONSTRUCTION.
- THE RETENTION/SEDIMENT BASIN WILL BE CONSTRUCTED AND MAINTAINED BY THE OPERATOR. THE MAINTENANCE OF THIS BASIN WILL BE TRANSFERRED TO THE PERMITTEE UPON THE COMPLETION OF FINAL STABILIZATION.
- 3. THE OPERATOR IS RESPONSIBLE FOR PROVIDING DIVERSION TRENCHES, EROSION CHECKS, BERMS, ETC., OR OTHER MEANS OF ACCEPTED PRACTICE AS REQUIRED ON THE SITE TO PREVENT ACCELERATED RUNOFF AND EROSION, WHICH MAY NOT BE INDICATED, BUT IS WITHIN THE TRIBED OF THIS BLAN.
- 5. SHOULD ANY MEASURES CONTAINED WITHIN THIS PLAN PROVE INCAPABLE OF ADEQUATELY REMOVING SEDIMENT FROM ON-SITE FLOWS PRIOR TO DISCHARGE OR OF STABILIZING THE SURFACES INVOLVED, ADDITIONAL MEASURES MUST BE IMMEDIATELY IMPLEMENTED BY THE OPERATOR TO ELIMINATE ALL SUCH PROBLEMS.
- 6. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S OR MODIFICATIONS TO THOSE INSTALLED WILL BE REGUIRED.
- THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THIS SITE.
- 8. IT IS THE INTENT OF THIS PLAN TO MEET REQUIREMENTS OF SOIL EROSION CONTROL.
- 9. THE OPERATOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART I, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUB-PART C, PROTECTION OF NATURAL RESOURCES, ARTICLE II, WATER RESOURCES, CHAPTER 102 EROSION CONTROL.
- 10. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES.
- 11. AT ANY TIME PRIOR TO STABILIZATION SHOULD ANY E & S PROBLEMS OCCUR WHICH REQUIRE ADDITIONAL MEASURES, IMMEDIATE ACTION MUST BE TAKEN TO CORRECT THE PROBLEM.
- 12. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED.
- 13. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
- 14. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS TO BMP'S FOR GRADING AND ACQUIRING BORROW TO CONSTRUCT THOSE BMP'S.
- 15. AT STREAM CROSSINGS, 50 FOOT STREAM BANK BUFFER AREAS SHOULD BE MAINTAINED. ON BUFFERS, CLEARING, SOD DISTURBANCES, EXCAVATION, AND EQUIPMENT TRAFFIC SHOULD BE MINIMIZED. ACTIVITIES SUCH AS STACKING CUT LOGS, BURNING CLEARED BRUSH, DISCHARGING RAINWATER FROM TRENCHES, WELDING PIPE SECTIONS, REFUELING AND MAINTAINING EQUIPMENT SHOULD BE ACCOMPLISHED OUTSIDE OF BUFFERS. MULCHING
- MULCHING OF DISTURBED OR SEEDED AREA SHALL BE FURNISHED, PLACED, ANCHORED AND MAINTAINED IN ACCORDANCE WITH PENNDOT PUBL. 408, SECTION 805. 2. MULCHING SHALL BE PLACED IMMEDIATELY AFTER SEEDING OR WITHIN 48 HOURS AFTER SEEDING IS COMPLETE.
- HAY OR STRAW SHALL BE UNIFORMLY PLACED IN A CONTINUOUS BLANKET, AT A MINIMUM RATE OF 3.0 TONS PER ACRE.
- MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS SHOULD BE INSTALLED ON ALL SLOPES 3: 1 OR STEEPER.
- 5. STRAW MULCH SHOULD BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN
- SEEDING
- 1. SEEDING SHALL BE PLACED IN ACCORDANCE WITH PENNDOT PUBL. 408, SECTION 804. SEED FORMULAS:

FORMULA AND SPECIES	% BY WT	MIN. % PURITY	MIN. % GERMIN- ATION	MAX. % WEED	SEEDING RATE LBS/1000 SQ. YDS.
FORMULA B * PERENNIAL RYEGRASS MIXTURE * CREEPING RED FESCUE OR CHEWINGS FESCUE	20 30	98 98	90 85	0.15 0.15	21.0 TOTAL 4.0 6.0
* KENTUCKY BLUEGRASS MIXTURE	50	98	80	0.20	11.0
FORMULA C * CROWNVETCH * ANNUAL RYEGRASS	45 55	99 98	70 90	0.10 0.15	9.0 TOTAL 4.0 5.0
FORMULA D * TALL FESCUE * CREEPING RED FESCUE OR CHEWINGS FESCUE	70 30	98 98	85 85	0.15 0.15	21.0 TOTAL 15.0 6.0
FORMULA E * ANNUAL RYEGRASS	100	98	90	0.15	10.0 TOTAL 10.0
FORMULA L * HARD FESCUE MIXTURE * CREEPING RED FESCUE * ANNUAL RYEGRASS	55 35 10	98 98 98	85 85 90	0.15 0.15 0.15	24.0 TOTAL 13.0 8.5 2.5
FORMULA W * TALL FESCUE * BIRDSFOOT TREFOIL MIXTURE * REDTOP	70 20 10	98 98 92	85 80* 80	0.15 0.10 0.15	10.5 TOTAL 7.5 2.0 1.0

* MINIMUM 20% HARD SEED AND 60% NORMAL SPROUTS

3. APPLICATION DATES: MARCH 15 TO JUNE 15 AUGUST 1 TO OCTOBER 15 FORMULA B, D, & L FORMULA C MARCH 1 TO OCTOBER 15

CROWNVETCH PORTION: ANYTIME EXCEPT SEPTEMBER & OCTOBER

FORMULA E MARCH 15 TO OCTOBER 15 APRIL 1 TO JUNE 15 AUGUST 16 TO SEPTEMBER 15 FORMULA W

4. SOIL SUPPLEMENTS MAY BE ADDED IN ACCORDANCE WITH SECTION 804 OR AS FOLLOWS: FERTILIZER - STANDARD QUALITY 0-20-20 BASIC FERTILIZER 10-10-10 STARTER FERTILIZER


LIME - AGRICULTURAL LIMESTONE 90% MINIMUM OF CARBONATES 500 LBS. PER 1000 S.Y.

5. FORMULA B SHALL BE USED TO ESTABLISH FINAL VEGETATION IN LAWN AREAS, FORMULA D SHALL BE USED TO ESTABLISH FINAL VEGETATION IN ROUGH AREAS, AND FORMULA E SHALL BE USED TO ESTABLISH TEMPORARY VEGETATION. FORMULAS C, L, AND W SHALL BE USED AS SPECIFICALLY INDICATED ON THE PLAN.

- G. SEEDING AND MULCHING SCHEDULE
- THE DIVERSIONS, CHANNELS, SEDIMENT BASINS, SEDIMENT TRAPS, AND STOCKPILES, WHEN USED, MUST BE STABILIZED IMMEDIATELY.
- IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS
- AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS
- H. UTILITY LINE TRENCH EXCAVATION

2. EXCEPTIONS


- LIMIT ADVANCE CLEARING AND GRUBBING OPERATIONS TO A DISTANCE EQUAL TO TWO TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE
- B. WORK CREWS AND EQUIPMENT FOR TRENCHING, PLACEMENT OF PIPE, PLUG CONSTRUCTION AND BACKFILLING WILL BE SELF CONTAINED AND SEPARATE FROM CLEARING AND GRUBBING AND SITE RESTORATION AND STABILIZATION OPERATIONS
- C. LIMIT DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE PLACEMENT, PLUG INSTALLATION AND BACKFILLING THAT CAN BE COMPLETED IN THE SAME DAY.
- D. WATER WHICH ACCUMULATES IN THE OPEN TRENCH WILL BE COMPLETELY REMOVED BY PUMPING BEFORE PIPE PLACEMENT AND/OR BACKFILLING BEGINS. WATER REMOVED FROM THE TRENCH SHALL BE PUMPED THROUGH A FILTRATION DEVICE.
- E. ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS AND IMMEDIATELY STABILIZED. F. ALL SOIL EXCAVATED FROM THE TRENCH WILL BE PLACED ON THE UPHILL SIDE OF THE TRENCH.
- G. SOILS EXCAVATED FROM EXISTING SURFACE LAYER SHOULD BE STOCKPILED SEPARATELY AND RETURNED AS FINAL SURFACE LAYER FOLLOWING TRENCH BACKFILLING.
- TRENCH PLUGS WILL BE SPACED IN ACCORDANCE WITH AND BE CONSTRUCTED OF THE MATERIALS AS INDICATED ON THE TRENCH PLUG DETAIL.
- (1) AT ALL CROSSINGS OF WATERS OF THE COMMONWEALTH, TRENCH PLUGS WILL BE INSTALLED AT THE BANKS AFTER TRENCH EXCAVATION. THE PLUGS MAY BE TEMPORARILY REMOVED WHEN PLACING THE PIPE, BUT THEN
- (2) CONSTRUCTION OF THE CROSSING WILL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE "PIPELINES AND UTILITY LINE PROJECTS" SECTION OF THE EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL
- IN CERTAIN CASES TRENCHES CANNOT BE BACKFILLED UNTIL THE PIPE IN HYDROSTATICALLY TESTED, OR ANCHORS AND OTHER PERMANENT FEATURES INSTALLED. IN THESE CASES, ALL OF THE REQUIREMENTS LISTED UNDER ITEM 1 WILL REMAIN IN EFFECT WITH THE
- 1C. DAILY BACKFILLING OF THE TRENCH MAY BE DELAYED FOR SIX DAYS. ALL PRESSURE TESTING AND THE COMPLETE BACKFILLING OF THE OPEN TRENCH MUST BE COMPLETED BY THE SEVENTH WORKING DAY
- 1E. IF DAILY BACKFILLING IS DELAYED, THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS, APPROPRIATE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES/FACILITIES WILL BE INSTALLED, AND THE AREAS SEEDED AND MULCHED WITHIN THE NEXT TWO CALENDAR DAYS.
- IF THE SITE WILL NEED TO IMPORT OR EXPORT MATERIAL FROM THE SITE, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND DETERMINATION OF CLEAN FILL WILL REST WITH THE CONTRACTOR.
- CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE).
- CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULA TED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- 4. ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS.
- . ENVIRONMENTAL DUE DILIGENCE: THE APPLICANT MUST PERFORM ENVIRONMENTAL DUE DILIGENCE TO DETERMINE IF THE FILL MATERIALS ASSOCIATED WITH THE PROJECT QUALIFY AS CLEAN FILL. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULA TED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE. THESE REGULATIONS ARE AVAILABLE ON-LINE AT WWW.pacode.com.



STANDARD CONSTRUCTION DETAIL #3-16 PUMPED WATER FILTER BAG


LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE STANDARDS LISTED INTHE EROSION AND A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREAS, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES GREATER THAN 5%. CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED THE PAGE TO DECLIFE SLOPE STEEPINESS. NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAIALBLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHOULD BE NO GREATER THAN 750 GPM OR 1/2 RHE MAXIMUM SPECIFIED SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHOULD BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.



TREE PROTECTION SPECIFICATIONS

- A 4" layer of coarse mulch or woodchips is to be placed beneath the drip line of the protected trees. Mulch is to be kept 12" from the trunk.
- II. A protective barrier of 6 foot chain link fencing shall be installed around the drip line of protected tree(s). The fencing can be moved within the drip line if authorized by the Consulting Arborist but not closer than 2 feet from the trunk of any tree. Fence posts shall be 2 inches in diameter (and are to be driven 2 feet into the ground. The distance between posts shall not be more then 10 feet. This enclosed area is the Tree Protection Zone (TPZ).
- III. Movable barriers of chain link fencing secured to concrete blocks can be substituted for "fixed" fencing if the Consulting Arborist agrees that the fencing will have to be moved to accommodate certain phases of construction. The builder may not move the fence without authorization from the Consulting Arborist Consulting Arborist.
- IV. Where the Consulting Arborist has determined that tree protection fencing will interfere with the safety of work crews, Tree Wrap may be used as an alternative form of tree protection. Wooden slats at least one inch thick are to be bound securely, edge to edge, around the trunk. A single layer or more (of orange plastic construction fencing is to be wrapped and secured around the outside of the wooden slats. Major scaffold limbs may require protection as determined by the Consulting Arborist. Straw waddle may also be used as a trunk wrap by coiling the waddle around the trunk up to a minimum height of six feet from grade. A single layer or more of orange plastic construction fencing is to be wrapped and secured around the straw waddle.



FLOW LINE

STOCKPILE

ELEVATION

_EXTEND FOR 8' UPSLOPE @ 45°

STANDARD FILTER

(18" HIGH - TYP)

STANDARD FILTER - FABRIC FENCE

(18" HIGH - TYP)

* STAKES SPACED @ 8' MAXIMUM. USE 2"X2"X48"(+/-3/8") WOOD OR EQUIVALENT STEEL (U OR T) STAKES. FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL.

FABRIC WIDTH SHALL BE 42" MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) SATKES. AN 18" SUPPORT STAKE SHALL BE DRIVEN 12" MINIMUM INTO UNDISTURBED GROUND. SILT FENCE SHALL BE INSTALLED AT EXISTING LEVEL GRADE. BOTH ENDS OF FENCE SECTION SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.

<u>6" MIN</u>.


6" MIN

TOE ANCHOR

x segmm. Estor

SEDIMENT SHALL BE REMOVED WHERE ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEE STANDARD CONSTRUCTION DETAIL #4-6.


STANDARD CONSTRUCTION DETAIL #4-8 REINFORCED SILT FENCE (30" HIGH) (NTS)




REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE. RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK ENTRANCE . MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED.PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED MAINTENANCE

ROCK CONSTRUCTION ENTRANCE THICKNESS WILL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL WILL BE MAINTAINED ON THE SITE FOR THIS PURPOSE. ANY SEDIMENT LOCATED ON THE PUBLIC ROADWAY SHOULD BE REMOVED IMMEDIATELY AND RETURNED TO THE CONSTRUCTION SITE.

STANDARD CONSTRUCTION DETAIL #3-1 ROCK CONSTRUCTION ENTRANCE (NTS)



JOINING FENCE SECTIONS




ELEVATION VIEW

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3. FABRIC WIDTH SHALL BE 30" MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEE STANDARD CONSTRUCTION DETAIL #4-6. FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY ARE IS PERMANENTLY STABILIZED

STANDARD CONSTRUCTION DETAIL #4-7 STANDARD SILT FENCE (18" HIGH)

(SF18)



MANHOLES 1 & 2

02-05-16 REV DETAILS 12-22-15 REV PER TWP. REVIEW REVISION NO. DATE REVISIONS REGISTERED // PROFESSIONAL / JOSEPH M. ESTOCK UNDERGROUND UTILITIES ENGINEER / PA. ACT 187 OF 1996-ONE CALL NOTIFICATION (1-800-242-1776) DATE: 04-16-15 SERIAL NO.: 20151062204 ALL LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLAN HAVE BEEN DEVELOPED FROM EXISTING UTILITY CO. RECORDS AND/OR ABOVE GROUND EXAMINATION OF THE SITE. COMPLETENESS OR ACCURACY OF LOCATION AND DEPTH OF UNDERGROUND UTILITIES OR STRUCTURES IS NOT GUARANTEED NOR IS IT GUARANTEED THAT ALL EXISTING UTILITIES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXISTENCE OF UTILITIES AND FOR NOTIFYING THE UTILITY COMPANIES AT LEAST THREE (3) WORKING DAYS PRIOR TO THE START OF CONSTRUCTION TO VERIFY LOCATION AND DEPTH OF SAME.

PROJECT TITLE .

131-133 GARRETT AVENUE


RADNOR TOWNSHIP - DELAWARE COUNTY - PENNSYLVANIA


EROSION AND SEDIMENT CONTROL NARRATIVE AND DETAILS


PREPARED BY :

355 South Henderson Road


JOSEPH M. ESTOCK King of Prussia, PA 19406-2407 265-3035 - Fax (610) 962-9855 Consulting Engineers & Land Surveyors joe@josephmestock.com DATEFILE NO. | FIELD BOOK | SHT. NO. *27 APRIL 2015* 327 AS NOTED









V2.0





L9.0



ELEVATION VIEW

NOTES: FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL MANUAL. FABRIC WIDTH SHALL BE 42 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. AN 18 IN.

SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP

SUPPORT STAKE SHALL BE DRIVEN 12 IN. MINIMUM INTO UNDISTURBED GROUND.


SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

FENCE NO.	LOCATION	SLOPE PERCENT	SLOPE LENGTH ABOVE BARRIER (FT)
RSF-I	WEST OF PARKING AREA	2.67%	300'
RSF-2	SOUTH OF RSF-I	2.76%	271'
RSF-3	EAST OF BALLFIELD	3.00%	351'
RSF-4	BELOW TOPSOIL STOCKPILE	2.48%	242'
RSF-5	WEST OF RSF-4	4.00%	50'
RSF-6	SOUTH OF TENNIS COURTS AND NEW PAVILLION	3.11%	160.5'
RSF-7	SOUTHWEST OF NEW PAVILLION	3.21%	342'
RSF-8	SOUTH OF RSF-5	3.84%	265.5'
RSF-9	SOUTHWEST OF RSF-6	5.74%	184'

STANDARD CONSTRUCTION DETAIL #4-8 REINFORCED SILT FENCE (30" HIGH) CII.0 NOT TO SCALE

FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).



SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING


PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.


BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET

LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET. THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.


BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70 COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

STANDARD CONSTRUCTION DETAIL #11-1 E-4 TEROSION CONTROL BLANKET INSTALLATION










I. ALL WOODY VEGETATION TO BE RETAINED WITHIN 25 FEET OF A BUILDING SITE, PARKING AREA, DRIVEWAY OR OTHER PROPOSED IMPROVEMENT SHALL BE PROTECTED FROM EQUIPMENT DAMAGE BY FENCING OR OTHER EFFECTIVE BARRIERS APPROVED BY THE TOWNSHIP ENGINEER AND/OR ARBORIST. FENCING OR BARRIERS SHALL BE PLACED AS MUCH AS IS PRACTICAL AT THE DRIPLINE, LOCATION AND IMPROVEMENTS AS SHOWN ON THE PLANS. BARRIER LOCATION SHALL BE SUBJECT TO APPROVAL BY THE TOWNSHIP ENGINEER AND/OR ARBORIST. PROTECTION BARRIERS SHALL BE 6 FEET HIGH, CONSTRUCTED OF 2" CHAIN LINK MESH FABRIC. FABRIC SHALL BE SECURED TO 2" POSTS WITH 6 GA. ALUMINUM WIRE TIES AT 24" O.C. POST SHALL BE A MINIMUM OF 2 FEET IN THE GROUND AND SPACED 10 FEET ON CENTER MAX.

PLASTIC ZIP-TIES MAY NOT BE USED TO SECURE FABRIC TO POSTS.



LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG.WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEÓTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS. NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE


PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY

STANDARD CONSTRUCTION DETAIL #3-16 E-5 PUMPED WATER FILTER BAG


AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

TEN	IPORARY STABILIZA	ATION SEED MIX		
%	Botanical Name	Common Name	Seeding window	Application Rate
75	Secale cereale	Cereal Rye	Sept. 1 - Oct. 16	40 lbs./Acre
25	Lolium multiflorum	Annual Ryegrass		
		OR		
75	Avena sativa	Oats	May 1 - Sept. 15	40 lbs./Acre
25	Lolium multiflorum	Annual Ryegrass		-




I. FENCING SHALL BE FASTENED SECURELY TO THE T-POSTS. 2. FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION; ANY CHANGE TO THE LOCATION OF THE FENCING MUST BE APPROVED. 3. TEMPORARY GATES MAY BE UTILIZED TO ALLOW ACCESS TO CONSTRUCTION EQUIPMENT, BUT MUST BE CLOSED WHEN NOT IN USE






PLAN VIEW



SECTION A-A


MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLYMAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE

STANDARD CONSTRUCTION DETAIL #3-I $^{\prime}$ E-6 $^{\prime}$ ROCK CONSTRUCTION ENTRANCE



PA 042324

C12.0



S i t ebushohocken, PA 19428

Facsimile: 610.834.7815

IMMEL BOGREIII rchitecture + Site

Architectu

RADNOR MEMORIAL LIBRARY
RENOVATION & EXPANSION
PRELIMINARY / FINAL LAND DEVELOPMENT
PLANS

Checked By: KG/BE

Scale: I" = 20'

ions:
U5.16 TWP COMMENTS
Chec

s Prints:
Revisions:
A 2.15.16 TWP C

VI.0 OF 14

TREE REMOVAL SCHEDULE		LEGEND
BOTANICAL NAME COMMON NAME SIZE (DBH) REQ'D REPLACEMENT TREES NOTES ACER PALMATUM JAPANESE MAPLE 4" 0 ACER SACCHARINUM SILVER MAPLE 12" 1 FRAXINUS SPP. ASH SPECIES 12" 1 FRAXINUS SPP. ASH SPECIES 18" 1 QUERCUS PALUSTRIS PIN OAK 48" 6 4 OF 6 T TOTAL REQ'D REPLACEMENT TREES 9 MIN. REQ'D CANOPY TREES 4	TO BE CANOPY TREES	
		EXISTING UTILITY POLE SW SW SW EXISTING STORMWATER EXISTING EDGE OF PAVEMENT EXISTING CURB EXISTING SIDEWALK CENTERLINE ROAD RIGHT-OF-WAY LINE PROPERTY LINE ADJOINER
	CARTWAY 25' FRONT YARD SETBACK ROW. LINE 12" FRAXINUS SPP. ASH SPECIES 18" FRAXINUS SPP. ASH SPECIES 18" FRAXINUS SPP. ASH SPECIES 18" ACER PLATANOIDES NORWAY-MAPLE 12" ACER SACCHARINUM 5ILVER MAPLE ITBR: 12" ACER SACCHARINUM 5ILVER MAPLE ITBR: 12" ACER SACCHARINUM 5ILVER MAPLE ITBR: 12" JUGLANS NIGRA BLACK WALNUT 12" ACER SACCHARINUM 5ILVER MAPLE 15' SIDE AND REAR SETBACK 1	EXISTING FENCE EASEMENT
	18" SOPHORA JAPE SOPHORA TREE	DIVICA
	FF SUB LEVEL=377.18" FF SUB LEVEL=377.23" FF SUB LEVEL=377.23" FF SUB LEVEL=377.23"	
	36° QUERCUS PIN DAK PIN DAK 4" AGER PALMATI JAPANESE MAPU	
	18" FRAXINUS SPP. ASH SPECIES TBR	
	6° PRUNUS SPP. CHERRY SPECIES 8° ACER PSEUDOPLATANUS SYCAMORE MAPLE 12" PYRUS CALLERYANA FLOWERING PEAR 12" PYRUS CALLERYANA	
	12" PYRUS CALLERYANA FLOWERING PEAR	
OWNER: RADNOR TOWNSHIP 301 IVEN AVENUE WAYNE, PA 19087		
PHONE: 610-688-5600 CONTACT: STEVE NORCINI EMAIL: SNORCINI@RADNOR.ORG		0' 20' 40' SCALE: 1" = 20'

Φ

•—

S

r c h i


NG CONTOUR MINOR ING WATER LINE NG GAS LINE NG SEWER LINE & MANHOLE NG OVERHEAD ELECTRIC NG UNDERGROUND ELECTRIC NG COMMUNICATIONS ING UTILITY POLE NG STORMWATER

RADNOR MEMORIAL LIBRARY
RENOVATION & EXPANSION
PRELIMINARY / FINAL LAND DEVELOPMENT
PLANS
I14 WEST WAYNE AVENUE
WAYNE, PA 19087

Checked By:

Sheet Name: SHADE TREE PLAN
Progress Prints:
A 2.15.16 TWP COMMEN
A 2.15.16 TWP COMMEN
A 2.15.16 TWP COMMEN
A 2.15.16 TWP COMMEN
A 3.15.16 TWP COMMEN
A 4.15.16 TWP COMMEN
A 5.15.16 TWP COMMEN
A 5.15

OF 14




KEY	BOTANICAL NAME	COMMON NAME	QTY	SIZE	CONDITION	SPACING	GC 1	GC 2	GC 3	GC 4
CP	CAREX PENSYLVANICA	PENNSYLVANIA SEDGE	58	QUART	CONTAINER	18"	16	13	18	12
		SPRING FLOWERING BULBS	44				12	10	14	9
EP	ECHINACEA PURPUREA	PURPLE CONEFLOWER	29	QUART	CONTAINER	18"	8	5	12	4
EA	ECHINACEA PARADOXA	YELLOW CONEFLOWER	24	QUART	CONTAINER	18"	5	6	6	7
RL	RUDBECKIA MAXIMA	GREAT CONEFLOWER	21	QUART	CONTAINER	18"	7	5	6	. 3
							47	20		٦.

PLANT SCHEDULE - TREES AND SHRUBS

KEY	BOTANICAL NAME	COMMON NAME	QTY	SIZE	CONDITION	NOTES
AR	ACER RUBRUM	RED MAPLE	3	2-2.5"	B&B	
BN	BETULA NIGRA	RIVER BIRCH	1	2-2.5"	B&B	MULTI-STEN
FG	FOTHERGILLA GARDENII	DWARF FOTHERGILLA	31	QUART	CONTAINER	
HV	HAMAMELIS VIRGINIANA	WITCHHAZEL	1	#7	CONTAINER	
HQ	HYDRANGEA QUERCIFOLIA	OAKLEAF HYDRANGEA	22	#3	CONTAINER	
IG	ILEX GLABRA	INKBERRY	60	#3	CONTAINER	
IV	ILEX VERTICILLATA	WINTERBERRY	5	#3	CONTAINER	
LA	LEUCOTHOE AXILLARIS	LEUCOTHOE	14	#3	CONTAINER	
RA	RHODODENDRON ARBORESCENS	SMOOTH AZALEA	5	#3	CONTAINER	
TC	TSUGA CANADENSIS	CANADIAN HEMLOCK	5	6-8'	B&B	
VD	VIBURNUM DENTATUM	ARROWWOOD VIBURNUM	5	#3	CONTAINER	
VN	VIBURNUM NUDENS	POSSUMHAW VIBURNUM	5	#3	CONTAINER	

PLANT SCHEDULE - SCREENING

KEY	BOTANICAL NAME	COMMON NAME	QTY	SIZE	CONDITION	SPACING
СН	CHASMANTHIUM	NORTHERN SEA OATS	38	QUART	CONTAINER	36"





PROPOSED SHRUB

O


OF 14

OWNER:

RADNOR TOWNSHIP 301 IVEN AVENUE WAYNE, PA 19087 PHONE:

610-688-5600 STEVE NORCINI CONTACT:

SNORCINI@RADNOR.ORG **EMAIL**:



MAXIMUM DRAINAGE AREA = 1 2 ACRE.

INLET PROTECTION SHALL NOT BE REDUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REDUIRED FOR ALL INSTALLATIONS.


ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILI□ATION IS COMPLETED OR REMAIN PERMANENTLY.


AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPE OIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.


INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HA□ARDS.

STANDARD CONSTRUCTION DETAIL #4-16 FILTER BAG INLET PROTECTION - TYPE M INLET







- DO NOT:


 1. ALLOW RUN OFF OF SPILLAGE AND DAMAGING MATERIALS INTO THE AREA BELOW ANY TREE CANOPY,

 2. STORE MATERIALS, STOCKPILE SOIL, OR PARK OR DRIVE VEHICLES WITHIN THE TP.,
- 3. CUT, BREAK, SKIN, OR BRUISE ROOTS, BRANCHES, OR TRUNKS WITHOUT FIRST OBTAINING AUTHORIDATION FROM THE CONSULTING ARBORIST,
- 4. ALLOW FIRES UNDER AND ADJACENT TO TREES,
- DISCHARGE EXHAUST INTO FOLIAGE, 6. SECURE CABLE, CHAIN, OR ROPE TO TREES OR SHRUBS,
- 7. TRENCH, DIG, OR OTHERWISE EXCAVATE WTIHIN THE DRIPLINE OR TP OF THE TREE SOWITHOUT FIRST OBTAINING AUTHORIDATION FROM THE CONSULTING ARBORIST,
- 8. APPLY SOIL STERILANTS UNDER PAVEMENT NEAR EXISTING TREES.

- TREE PROTECTION NOTES

 1. A 4" LAYER OF COARSE MULCH OR WOODCHIPS IS TO BE PLACED BENEATH THE DRIPLINE OF THE PROTECTED TREES. MUCH IS TO E KEPT 12" FROM THE TRUNK. 2. A PROTECTIVE BARRIER OF 6' CHAIN LINK FENCING SHALL BE INSTALLED AROUND THE DRIPLINE OF PROTECTED TREE S THE FENCING CAN BE MOVED WITHIN THE DRIPLINE IF AUTHORI□ED BY THE CONSULTING ARBORIST, BUT NOT CLOSER THAN
- 2' INTO THE GROUND. THE DISTRANCE BETWEEN POSTS SHALL NOT BE MORE THAN 10'. THIS ENCLOSED AREA IS THE TREE PROTECTION ONE TPOD . MOVABLE BARRIERS OR CHAIN LINK FENCING SECURED TO CEMENT BLOCKS CAN BE SUBSTITUTED FOR "FIXED" FENCING IF THE CONSULTING ARBORIST AGREE THAT THE FENCING WILL HAVE TO BE MOVED TO ACCOMODATE CERTAIN PHASES OF
- CONSTRUCTION. THE BUILDER MAY NOT MOVE THE FENCE WITHOUT AUTHORI□ATION FROM THE CONSULTING ARBORIST. 4. WHERE THE CONSULTING ARBORIST HAS DETERMINED THAT TREE PROTECTION FENCING WILL INTERFERE WITH THE SAFETY OF WORK CREWS, TREE WRAP MAY BE USED AS AN ALTERNATIVE FORM OF TREE PROTECTION. WOODEN SLATES AT LEAST ONE ☑ □INCH THICK ARE TO BE BOUND SECURELY, EDGE TO EDGE, AROUND THE TRUNK. A SINGLE LAYER OR MORE OF ORANGE CONSTRUCTION FENCING IS TO BE WRAPPED AND SECURED AROUND THE OUTSIDE OF THE WOODEN SLOTS. STRAW WADDLE MAY ALSO BE USED AS A TRUNK WRAP BY COILING THE WADDLE AROUND THE TRUNK UP TO A MINIMUM HEIGHT OF SIX 16 FEET FROM GRADE. A SINGLE LAYER OR MORE OF ORANGE PLASTIC CONSTRUCTION FENCING IS TO BE WRAPPED AND SECURED AROUND THE STRAW WADDLE.





OF 14





RADNOR TOWNSHIP SHADE TREE COMMISSION

Hazardous Tree Report

Resident Dave Falcone
Address 836 Milmar Rd Newtown Square 19073
Tree (Type, species, size, diameter at breast height) White Ash 36" DBH, Silver Maple 32" DBH, Tulip Poplar 42" DBH, and ~15 Understory trees /small sapling
Certified arborist's narrative report (attach separate sheet if required) Attached
Certified arborist's name, address and # Marc Conady 907 Fagewood Terrence Wilmington, DE 19809 302 545 8225
Pictures attached Plot plan drawing attached
Township arborist's report (attach separate sheet if required)

Shade Tree Commission removal recommended yes (no)



The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.

White ash 36" DBH Front of home

Tree has large overextended leaders over the roof. Many branches have existing dead tips that indicate decline and possible Emerald Ash Borer infestation. Branch reductions would leave large stub cuts that are not practical to heal over in a reasonable amount of time.

Silver Maple 32" DBH Behind Home


Tree had previous lightning strike that has not formed callous tissue to seal damage. Open face decay began to form at location of damage. Decay fungus fruiting structures formed on trunk in areas of decay. Most likely Ganoderma a common decay fungi. This causes structural issues and makes the tree more likely to fail.


Tulip Poplar 42" DBH Back Rear


Tree had a high live crown ratio and poor trunk taper from developing in the woods. Surface roots showed signs of cavities and decay. Damage was likely caused by mechanical damage. Due to the rapid growth and poor root system the tree is more likely to fail in a storm causing extensive property damage. Poplar trees are known to be poor comparmentalizers and have low wood density.


Radnor Township Engineering Department

	eld Report	
301 Iven Avenue, Wayne PA 19087-5297	610.688.5600	610.971.0450 (fax)
ADDRESS/SITE_836 MIL	MAR	
nspector:	Weather Condition	ons SOMMY SO
ime in: Time Out:	Date :	2 9 9 1 5
mic m mic out		Stewart of China Control of Stewart
	Inspection	
&S Escrow SWM SS Pavi	ing Other/Complaint	
Present at Site		
votes: & 34	The same	
(24) (13/25)	and the second s	
<u> </u>		
		- 14 Francis
	** 11 Score Land & Marie Land	
834		
		<u>Stance</u>
		- NO ONE WH
		1002000
		CAMEDSOE
h magnete the fit will be the	e to be all or a superior	<i>t</i> .
ACTION ITEMS	STUMP GROUND	
	Mack ousing ,	sawnide stumps
I TOLD HIMMADRE REI	MONAL + GANE	
THATE DUE ON THE D	dor of the Ho	g geological de la constant de la co




































































STROBER STROBER STROBER Clearing Operations (302) 656-6077

USDOT1287979













RADNOR TOWNSHIP SHADE TREE COMMISSION

Resident Radner Station off a Blb

Addition 190 King of Grosen Bld

Tree (Type, species, size, diameter at breast height) 1 40" cal Ash tree

Certified arborist's marrative report (attach separate sheet if required)

Tree 15 In Decline, Tox 15 MI Dave and 1

Tree 15 located on left Side of Bld Z

Certified arborist's name, address and # Robert & Bescome
201 Hansell Rd Mentaun Sq 19073

Pictures attached _____ Plot plan drawing attached _____ Township arborist's report (attach separate sheet if required) _____ Plot plan drawing attached ______ Plot

Shade Tree Commission removal recommended yes / no

The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.

