Shade Tree Commission of Radnor Township Wayne, Pennsylvania

AGENDA

Wednesday July 22, 2015 6:30 PM

115 Strafford Avenue

Discussion regarding trees and shrubs compromised due to construction

- (6) white pines need to be removed at the Township Arborist's request
- (9) 14-16' Norway Spruce Trees need to be planted for these removals in September

Discussion: amending the Shade Tree Ordinance section 263-6 Emergency Tree Removal

220 Lansdowne Avenue GP # 15-117 Addition, walks and driveway 195 CY of dirt (take off site)

411 Louella Avenue GP # 15-119

Addition, patio, drive, deck, etc

- (3) trees to be removed (2) 8" & (1) 10"
- (3) trees will be planted 475 CY of dirt (take off site)

446 Boxwood Road GP # 15-120

Construct single family dwelling 1,500 CY of dirt (take off site)

14 trees to be removed (7) 6-18" (5) 19-29" (2) 30"+

34 trees required – 18 being large canopy

36 trees provided – 20 being large canopy

Ravenscliff / Roundhill GP # 15-121

Pond dredging

2,500 CY of dirt (keep on site)

Hazardous Tree Removals Approved for removal by Township Arborist

743 King of Prussia Road

50" Black Oak

Signs of decline throughout canopy and does not have a healthy root flair at base Tree is located behind house

Applicant's arborist was asked to have applicant plant 1 large canopy tree

304 Landover Road

31" Red Oak

Decay on central leader @ 30', slight crack or opening along trunk, possibly due to June wind storm

320 Louella Avenue 37" Sugar Maple Significant rot and decay in trunk Township Arborist requested (1) shade tree be planted

312 West Avenue

20" Hemlock


13" Cedar


26" White Pine substantial 18" x 30" rotted section 25' up on the trunk


(2) 10" Cedar

12" Cedar

All trees are growing within 1-2' of foundation of house. Root systems are pushing against the foundation causing cracks and allowing water to penetrate into the basement. Trees are declining and unbalanced. Trimming the trees is not an option







OPERATION AT A MINIMUM, THE FOLLOWING SCHEDULE OF OPERATION AND MAINTENANCE PROCEDURES FOR VEGETATED SWALES SHALL BE FOLLOWED: OBSERVATIONS SHALL BE MADE TO DETERMINE THE LENGTH OF TIME NEEDED FOR RETAINED WATER TO INFILTRATE INTO THE SOIL AFTER A STORM EVENT. THE OBSERVATIONS SHALL BE MADE BY READING THE WATER LEVEL IN THE INLET BOX(ES) OF THE UNDERGROUND SYSTEM(S) SEVERAL TIMES OVER A PERIOD OF TWO (2) DAYS AFTER A LARGE STORM EVENT. THE FIRST OF THESE OBSERVATIONS SHALL PROVIDE A RECORD OF HOW WELL THE SYSTEM IS WORKING WHEN COMPARING FUTURE OBSERVATIONS. MEASUREMENTS SHOULD BE TAKEN AFTER EACH RAIN EVENT OF 0.5—INCHES OR MORE, OR MONTHLY, AS DETERMINED BY LOCAL WEATHER CONDITIONS. AT A MINIMUM, OBSERVATIONS SHALL BE MADE TWICE THE FIRST YEAR AND YEARLY THEREAFTER. MONITOR SEDIMENT ACCUMULATIONS IN ALL STORMWATER MANAGEMENT AND WATER QUALITY FACILITIES. REMOVE SEDIMENT IF STORAGE VOLUMES HAVE BEEN REDUCED SIGNIFICANTLY OR THE POOLS BECOME STAGNANT. ACCUMULATED SEDIMENT SHALL BE REMOVED FROM THE STORMWATER MANAGEMENT AND WATER QUALITY FACILITIES ON A REGULAR BASIS (EVERY 2 TO 10 YEARS FOR DRY DETENTION BASINS AND EVERY 5 TO 15 YEARS FOR WET POND FACILITIES) AND SHALL EITHER BE REMOVED FROM THE SITE OR DISPOSED OF ON—SITE AT AN APPROVED DISPOSAL AREA. MAINTENANCE OF CATCH BASINS AND INLETS IS BEST DONE MONTHLY WITH A VACUUM TRUCK. ALL COLLECTED WASTE MUST BE HANDLED AND DISPOSED OF ACCORDING TO LOCAL ENVIRONMENTAL REQUIREMENTS. PRIOR TO ON—SITE DISPOSAL OF SEDIMENT, THE OWNER SHALL ACQUIRE THE APPROPRIATE EARTH DISTURBANCE PERMITS FROM THE MUNICIPALITY AND/OR THE CONSERVATION DISTRICT. JAMES T. BRADLEY & EMILY ANDRIOLE, AS OWNER (S) OF THE SITE, ITS SUCCESSORS OR ASSIGNS SHALL BE RESPONSIBLE FOR THE PROPER MAINTENANCE OF ALL POST CONSTRUCTION STORMWATER MANAGEMENT FACILITIES AND RELATED ITEMS INCLUDED WITHIN THIS PLAN AND NARRATIVE. ALL STORMWATER MANAGEMENT AND WATER QUALITY FACILITIES SHALL BE INSPECTED QUARTERLY AND AFTER ALL MAJOR STORM EVENTS. ADDITIONALLY, A DETAILED INSPECTION BY A QUALIFIED INSPECTOR SHALL OCCUR AT ANNUALLY. MONTHLY MONITORING FOR THE FIRST YEAR AFTER THE SITE HAS BEEN STABILIZED IS RECOMMENDED. IF RESTORATION ACTIVITIES ARE REQUIRED, A SCHEDULE INDICATING THE DATE WHEN THE RESTORATION ACTIVITIES WILL BE STARTED AND COMPLETED SHALL BE COMPLETED. INSPECTIONS SHALL, AT A MINIMUM, INCLUDE: VEGETATED AREAS SHALL BE MAINTAINED WITH A MINIMUM UNIFORM VEGETATIVE 70% PERENNIAL VEGETATIVE COVER WITH A DENSITY CAPABLE OF RESISTING ACCELERATED EROSION AND SEDIMENTATION. VEGETATED AREAS THAT WASH OUT MUST BE FILLED AND GRADED AS NECESSARY AND THEN RESEEDED. AN ANCHORING METHOD SHOULD THEN BE USED TO HOLD SEED AND MULCH IN PLACE; THIS IS ESPECIALLY IMPORTANT AROUND WATER COURSES, IN SWALES, IN AREAS OF CONCENTRATED FLOWS, AND ON STEEP SLOPES. ALL STORMWATER MANAGEMENT FACILITIES SHALL BE CLEARED OF ALL DEBRIS AND LITTER ON A REGULAR BASIS AND AFTER ALL MAJOR STORM EVENTS. ADDITIONALLY, FLOATING DEBRIS SHALL BE REMOVED, AND THE FACILITY SHALL BE INSPECTED FOR VISIBLE POLLUTION OR SHORELINE PROBLEMS. ERODED CHANNELS OR AREAS OF EXCESSIVE EROSION NEAR THE FACILITY SHALL BE BACKFILLED AND STABILIZED IMMEDIATELY. OBSTRUCTIONS AND DEBRIS MAINTENANCE ACTIVITIES TO BE DONE ANNUALLY AND WITHIN 48 HOURS AFTER EVERY MAJOR STORM EVENT (> 1 INCH RAINFALL DEPTH): SUMPED INLETS SHALL BE INSPECTED AND SEDIMENT REMOVED ON A MONTHLY BASIS. A MINIMUM 6 INCH SUMP SHALL BE MAINTAINED IN ALL INLETS. A MINIMUM, OPERATION AND MAINTENANCE PROCEDURES FOR INFILTRATION BEDS SHALL CATCH BASINS AND INLETS SHOULD BE INSPECTED AND CLEANED AT LEAST 2 TIMES PER YEAR.

• THE OVERLYING VEGETATION OF SUBSURFACE INFILTRATION FEATURES SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS REVEGETATED AS SOON AS POSSIBLE.

• VEHICULAR ACCESS ON SUBSURFACE INFILTRATION AREAS SHOULD BE PROHIBITED, AND CARE SHOULD BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. IF ACCESS IS NEEDED, USE OF PERMEABLE, TURF REINFORCEMENT SHOULD BE CONSIDERED. INSPECT AND CORRECT EROSION PROBLEMS, DAMAGE TO VEGETATION, AND SEDIMENT AND DEBRIS ACCUMULATION (ADDRESS WHEN ACCUMULATION >3 INCHES AT ANY SPOT OR COVERING VEGETATION).
INSPECT VEGETATION ON SIDE SLOPES FOR EROSION AND FORMATION OF RILLS OR GULLIES, CORRECT AS NEEDED.
INSPECT FOR POOLS OF STANDING WATER; DEWATER AND DISCHARGE TO AN APPROVED LOCATION AND RESTORE TO DESIGN GRADE.
MOW AND TRIM VEGETATION TO ENSURE SAFETY, AESTHETICS, PROPER SWALE OPERATION, AND TO SUPPRESS WEEDS AND INVASIVE VEGETATION; DISPOSE OF CUTTINGS IN A LOCAL COMPOSTING FACILITY; MOW ONLY WHEN SWALE IS DRY TO AVOID RUTTING.
INSPECT FOR UNIFORMITY IN CROSS—SECTION AND LONGITUDINAL SLOPE, CORRECT AS NEEDED. INSPECTING FOR DAMAGE TO THE FACILITY.

ENSURE THE EMERGENCY SPILLWAY IS CLEAR OF OBSTRUCTIONS AND DEBRIS.

NOTE SIGNS OF HYDROCARBON BUILD—UP AND ADDRESS APPROPRIATELY.

MONITOR SEDIMENT ACCUMULATIONS IN ALL STORMWATER MANAGEMENT AND WATER QUALITY FACILITIES.

ENSURE INLET AND OUTLET DEVICES ARE FREE OF DEBRIS AND OPERATIONAL.

INSPECT FACILITIES FOR UNDESIRABLE VEGETATIVE OR WOODY GROWTH. PLANT ALTERNATIVE GRASS SPECIES IN THE EVENT OF UNSUCCESSFUL ESTABLISHMENT.

RESEED BARE AREAS; INSTALL APPROPRIATE EROSION CONTROL MEASURE WHEN NATIVE SOIL IS EXPOSED OR EROSION CHANNELS ARE FORMING.


ROTOTILL AND REPLANT SWALE IF DRAW DOWN TIME IS MORE THAN 48 HOURS. INSPECT AND CORRECT CHECK DAMS WHEN SIGNS OF ALTERED WATER FLOW (CHANNELIZATION, OBSTRUCTIONS, EROSION, ETC.) ARE IDENTIFIED.

WATER DURING DRY PERIODS, FERTILIZE, AND APPLY PESTICIDE ONLY WHEN ABSOLUTELY NECESSARY. INSPECT SWALE INLET (CURB CUTS, PIPES, ETC.) AND OUTLET FOR SIGNS EROSION OR BLOCKAGE, CORRECT AS NEEDED. PECT SWALE IMMEDIATELY AFTER THE SPRING MELT, REMOVE RESIDUALS (E.G. ND) AND REPLACE DAMAGED VEGETATION WITHOUT DISTURBING REMAINING SETATION.

GETATION.

ROADSIDE OR PARKING LOT RUNOFF IS DIRECTED TO THE SWALE, MULCHING ROADSIDE OR PARKING LOT RUNOFF IS DIRECTED IN THE SPRING TO DIVERSION STORE SOIL AERATION/MANIPULATION MAY BE REQUIRED IN THE SPRING TO STORE SOIL STRUCTURE AND MOISTURE CAPACITY AND TO REDUCE THE IMPACTS DEICING AGENTS.

ENONTOXIC, ORGANIC DEICING AGENTS, APPLIED EITHER AS BLENDED, MAGNESIULORIDE—BASED LIQUID PRODUCTS OR AS PRETREATED SALT. MAINTENANCE ACTIVITIES TO BE DONE DURING WINTER CONDITIONS: ACTIVITIES TO BE DONE AS NEEDED: MAINTENANCE STORMWATER MANAGEMENT & WATER QUALITY FACILITIES LAND N/F
DONALD L. HELMS & KIM HELMS-KERCHNER
APN: 36-03-01588-00
DB 4953, PG 1492
317 CONESTOGA ROAD STORMWATER PLAN CERTIFY TO THE BEST OF MY KNOWN ASSOCIATED BEST MANAGEMENT PRACTICES SHOWITH THE RADNOR TOWNSHIP STORMWATER NAME. I, HEREBY CERTIFY TO THE BEST OF MY KNOWLEDGE. THE EROSION & SEDIMENT CONTROL PLAN AND ASSOCIATED BEST MANAGEMENT PRACTICES SHOWN HEREON ARE DESIGNED IN CONFORMANCE WITH THE PENNSYLVANIA CHAPTER 102 EROSION & SEDIMENT CONTROL REGULATIONS. EROSION JUNE 30TH 2015 DATE JUNE 30TH2015 AND SEDIMENT 4.165 398.7 REBAR FOUND CONTR TOUND 9 PLAN 395.31NV 396.0 CERTIFICATION PROPOSED CLEANOUT
WITH LID 392.25 ω**,** PROPOSED FILLED
BOTTOMLESS INLET
- GRT = 395.50
INV = 392.60
SUMP = 389.00 X 20 X OF OF 5 59 28 53 PIPE OWNER'S I JAMES T. BRADLEY & EMILY ANDRIOLE HEREBY ACKNOWLEDGE THAT THE STORMWATER BMPS ARE FIXTURES THAT CAN BE ALTERED OR REMOVED ONLY AFTER APPROVAL BY THE MUNICIPALITY. (5 60.09 W) 392.25 GRAS 80 L.F 8" 393.00 393.50 ACKNOWLEDGEMENT PROPOSED GARAGE - INV = -396.20 35 LF OF 395.40 PROPOSED POP-UP EMITTER FOR EMERGENCY OVERFLOW N 59.46.10. E ₩ = 394.25 39A. ∞ OWNER'S SIGNATURES 2% SLOPE 397.8 (N 61-20:00° E) PROPOSED 2X2
YARD DRAIN
GRT = 394.50
INV = 392.50
SUMP =390.50 PROPOSED WITH LID 225.00 Ž LAND N/F GAYLA S. STEWART APN: 36-03-01706-00 222 LANSDOWNE AVENUE GM 1394/ 393.00 P.O + 398.5 ₩~ $\overline{\mathbb{Z}}$ (TBR) PROPOSED DRIVEWAY .[393] MADE LAND, GABBRO AND DIABASE MATERIALS 394.50 - PROPOSED CONCRETE SIDEWALK 3 Date 6/30/2015 Issued: -REBAR FOUND IRON PIPE FOUND POST DATED: SCALE: Heritage CONSTRUCTION STORMWATER MANAGEMENT 3.965 5/27/2015 Prilary 2 AS RADNOR NOTED BRADLEY220 W .05.72.0E/N 393.30 PENNSYLVANIA LAW REQUIRES THREE WORKING DAYS NOTICE PRIOR TO ANY EARTH MOVING ACTIVITIES WAYNE, ASH ASSOCIATES,
765 TENNIS AVENUE PENNSYLLA 392,90 LANSDOWNE AVENUE WWW.ASHASSOCIATES.NET DELAWARE COUNTY, AMBLER, PA 19002 PH: 215.367.5261 PA 19087 PROPERTY BEFORE J HNMOUSNYT SHEET PROJECT PENNSYLVANIA 4 MENDE NO. DIG! 0F 5 2756 PLAN



LINETYPE LEGEND - BUILDING SETBACK - FENCE LINE OVERHEAD ELECTRIC ELECTRIC LINE — GAS LINE — WATER LINE SANITARY LINE EXISTING STORM PIPES _ _ EXISTING 1' CONTOUR ____ EXISTING 5' CONTOUR

SYMBOL LEGEND

PROPERTY CORNER PROPERTY LINE STAKE

CLEANOUT LIGHT FIXTURE AIR CONDITIONING UNIT ELECTRIC METER

MAILBOX



SLOPES 20% AND GREATER

SLOPES 14% TO 20%

	.,			
GARAGE	388	S.F.		
DRIVEWAY	2,140	S.F.		
DECK	343	S.F.		
WALLS	163	S.F.		
WALKS/STEPS	961	S.F.		
TOTAL	5,293	S.F.	(22.80%)	

EXISTING IMPERVIOUS TO BE REMOVED:

PORTION OF RESIDENCE	234	S.F.
GARAGE	388	S.F.
DRIVEWAY	486	S.F.
DECK	343	S.F.
WALLS	86	S.F.
WALKS/STEPS	874	S.F.
TOTAL	2,411	S.F.

RADNOR TOWNSHIP ZONING HEARING BOARD

<u>APPEAL NO. 2939</u>

APPEAL OF KENNETH G. BARRINGER AND ELIZABETH L. WEBER, premises located at 411 Louella Avenue and zoned R-1. Appellants seek a variance from the restrictions of Zoning Code Section 280-15(D)(1) to allow aggregate side yards of 34.3 feet, a variance from the restrictions of Zoning Code Section 280-15(F) to allow impervious coverage of 28.46%, and a variance from Zoning Code Section 280—112(D) to allow expansion of a driveway backup area where there are steep slopes. In the alternative, Appellants contend that their proposed improvements are allowed by right.

DECISION OF THE ZONING HEARING BOARD

Variances under Zoning Code Sections 280-15(D)(1), 280-15(F), and 280- 112(D) are granted, the Order of the Zoning Officer is reversed, and an appropriate permit is ordered to be issued for the construction of Appellants' proposed addition and related improvements, in the precise location and manner as shown on that certain Site Improvement Plan (the "Plan") dated October 7, 2014 and last revised March 20, 2015, as prepared by R.H. Smith Surveyors, which Plan has been entered into the record as Appellants' Exhibit "A-14", and otherwise as shown on the plans, exhibits and testimony made part of the record, to the extent consistent with the Plan. Relief is granted only under Zoning Code Sections 280-15(D)(1), 280-15(F), and 280-112(D), and no relief is granted with respect to any other provision of the Zoning Code.

BY ORDER OF THE ZONING HEARING BOARD


/s/ BRADLEY DELIZIA, CHAIRMAN /s/ WILLIAM MARTIN, VICE-CHAIRMAN /s/ GEORGE NAGLE

/s/ JOHN REILLY /s/ MATTHEW HOMYK

JULY 1, 2015: THIS DECISION SHALL EXPIRE IF THE APPLICANT FAILS TO OBTAIN A BUILDING PERMIT WITHIN SIX (6) MONTHS FROM THIS DATE: JULY 1, 2015

SOILS INFORMATION ERODIBILITY HYDROLOGIC AGRICULTURAL LOAD DEPTH DEPTH GRAVEL SAND ROADFILL TOPSOIL ROADS AND RESERVOIR EMBANKMENTS IRRIGATION RESIDENTIAL LIGHT SEWAGE ON-SITE DEVELOPMENT INDUSTRIAL LAGOONS SEPTIC CAPABILITY DRAINAGE INDEX GROUP CLASS RATED RATED RATED RATED NOT RATED NO AND DIABASE NOT RATED NOT RATED 6.6+

NOTES: IF THE PROPOSED EROSION AND SEDIMENTATION CONTROL MEASURES ARE INSTALLED AND MAINTAINED PROPERLY, NO UNFORESEEN SOIL LIMITATIONS OR PROBLEMS ARE LIKELY. NEVERTHELESS, IF A PROBLEM DOES DEVELOP, THE DEVELOPER MUST TEMPORARILY SEED AND MULCH THE DISTURBED AREA. SUITABLE TOPSOIL SHALL BE IMPORTED TO SITE IF INADEQUATE QUANTITIES OF SUITABLE TOPSOIL EXIST ON SITE. ADEQUACY OF SOIL TO BE DÉTERMINED BY SITE GEOTECHNICAL ENGINEER IN CONJUNCTION WITH THE LANDSCAPE ARCHITECT. SOIL AMENDMENTS SHALL BE ADDED AS REQUIRED. ALL UNSUITABLE MATERIAL SHALL BE DISPOSED OF PROPERLY. SITE GEOTECHNICAL ENGINEER SHALL ALSO BE CONSULTED DURING WINTER GRADING OPERATIONS.



LOCATION MAP SCALE: 1" = 600

ZONING DISTRICT R-1 (RESIDENCE DISTRICT)

120' FEET MIN. AT BUILDING LINE LOT WIDTH 15% MAX. BLDG. AREA FRONT YARD 60 FEET MIN. 60 FEET AGG. (25 FEET MIN.) SIDE YARD REAR YARD 40 FEET MIN. 35 FEET MAX. IMPERVIOUS SURFACI 22% MAX. RIPARIAN BUFFER 35 FEET MIN.

FOR MORE DETAILED INFORMATION YOUR ATTENTION IS CALLED TO THE ZONING CODE OF RADNOR TOWNSHIP, LATEST EDITION.

10 FEET MIN.

GROSS LOT AREA = 23,216 S.F. (0.533 ACRES)

SOURCE OF TITLE:
DEED BOOK 5560 PAGE 2391
411 LOUELLA AVENUE WAYNE, PA 19087 TMP No. 36-03-01736-00

Block No. 21 Unit No. 72

ACCESSORY USE SETBACK:

GENERAL NOTES

- OWNER/APPLICANT: KENNETH G. BARRINGER & ELIZABETH L. WEBER 411 LOUELLA AVENUE WAYNE, PA 19087
- 2. BOUNDARY SURVEY AND EXISTING CONDITION INFORMATION TAKEN FROM A PLAN ENTITLED "SITE IMPROVEMENT PLAN" PREPARED BY R. H. SMITH SURVEYORS DATED OCTOBER 10 22, 2014, REVISED 03/20/15, PLAN No: 150301/140905
- 3. SOIL INFORMATION TAKEN FROM THE SOIL SURVEY FOR CHESTER AND DELAWARE COUNTIES PREPARED BY THE UNITED STATES DEPARTMENT OF AGRICULTURE.
- 4. THE PROPOSED DEVELOPMENT WILL INCLUDE THE DEMOLITION OF THE EXISTING DETACHED GARAGE, A PORTION OF THE EXISTING RESIDENCE AND THE CONSTRUCTION OF AN ADDITION TO THE EXISTING RESIDENCE WITH ATTACHED GARAGE, DRIVEWAY IMPROVEMENTS, AND OTHER ASSOCIATED IMPROVEMENTS TOGETHER WITH THE REMOVAL OF PORTIONS OF EXISTING PAVED AREAS.
- 5. THE CONSTRUCTION WILL RESULT IN SOME NEW AND REPLACEMENT IMPERVIOUS COVER FOR WHICH STORMWATER MANAGEMENT IS REQUIRED PER THE TOWNSHIP STORMWATER MANAGEMENT ORDINANCE.

7. THIS SITE IS CURRENTLY SERVED BY PUBLIC SEWER WHICH IS TO BE MAINTAINED AS PART OF THIS

- 6. THIS SITE IS CURRENTLY SERVED BY PUBLIC DOMESTIC WATER SERVICE. PUBLIC WATER SERVICE IS
- TO BE MAINTAINED.
- 8. MAINTENANCE FOR THE PROPOSED STORMWATER MANAGEMENT SYSTEM IS THE RESPONSIBILITY OF
- 9. UTILITY LINES SHOWN ARE APPROXIMATE. CONTRACTOR SHALL HAVE ALL LINES MARKED PRIOR TO CONSTRUCTION AND ADJUST SERVICES AS NECESSARY.
- 10. THE EXISTENCE AND/OR LOCATION OF ALL EXISTING AND PROPOSED SERVICES ARE APPROXIMATE AND MUST BE CONFIRMED INDEPENDENTLY WITH LOCAL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION OR EXCAVATION
- 11. THE CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF EXISTING TOPOGRAPHIC INFORMATION AND UTILITY INVERT ELEVATIONS PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION. ANY DISCREPANCIES THAT MAY AFFECT THE PUBLIC SAFETY OR PROJECT COST, MUST BE IDENTIFIED TO THE ENGINEER IN WRITING IMMEDIATELY. PROCEEDING WITH CONSTRUCTION WITH DESIGN DISCREPANCIES IS DONE SO AT THE CONTRACTOR'S OWN RISK.


ACKNOWLEDGE THAT ANY REVISION TO THE APPROVED DRAINAGE PLAN MUST BE APPROVED BY THE MUNICIPALITY.

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE THE EXISTING CONDITIONS ARE AS SHOWN AND THAT THIS DRAINAGE PLAN COMPLIES WITH ALL THE DESIGN STANDARDS AND CRITERIA OF THE RADNOR TOWNSHIP STORMWATER MANAGEMENT ORDINANCE.


DAVID R. FIORELLO, P.E. DATE








INC ASSOCIA! MOMENEE







SCALE: 1" = 20'

FILE NO.: 15-155

1 INCH = 20 FT.

ALL LOCATIONS OF EXISTING UTILITIES, SHOWN ON THIS PLAN, HAVE BEEN DEVELOPED FROM FIELD LOCATIONS OF VISIBLE ABOVE GROUND UTILITY STRUCTURES AND INFORMATION FURNISHED BY THE UTILITY

COMPLETENESS OR ACCURACY OF THE LOCATIONS AND DEPTH OF ALL

UTILITY COMPANIES THROUGH THE PENNSYLVANIA "ONE CALL SYSTEM"

STRUCTURES CANNOT BE GUARANTEED. CONTRACTORS MUST VERIFY

ALL LOCATIONS AND DEPTHS OF ALL UNDERGROUND UTILITIES AND

AS PER ACT 187 HOUSE BILL 2627, BEFORE THE START OF ANY EXCAVATION WORK THE CONTRACTOR SHALL NOTIFY THE AFFECTED

-800-242-1776 THREE DAYS PRIOR TO THE START OF ANY

EXCAVATION. THE CONTRACTOR SHALL VERIFY THE LOCATION AND

ALL LOCATIONS SHOULD BE CONSIDERED APPROXIMATE.

FACILITIES BEFORE THE START OF ANY WORK.

WITH A ONE FOOT SUMP BELOW THE INLET AND OUTLET PIPES SO THAT DEBRIS CAN BE COLLECTED PRIOR TO FLOWING INTO THE SUBSURFACE INFILTRATION BED.

THE SYSTEM IS DESIGNED TO PROMOTE GROUNDWATER RECHARGE. A CONTROL STRUCTURE WITHIN THE SYSTEM DISCHARGES TO A PROPOSED BUBBLE-UP SPREADER. AN ACCESS MANHOLE WITH A LADDER IS PROVIDED AT THE END OF THE SUBSURFACE PIPE SYSTEM TO FACILITATE ACCESS AND MAINTENANCE OF THE SYSTEM.

THE RESPONSIBILITY FOR THE CONTINUED OPERATION AND MAINTENANCE OF THE STORMWATER MANAGEMENT FACILITIES ON THIS LOT IS THAT OF THE PROPERTY OWNER.

1. THE OWNER, OCCUPANT, TENANT OR OTHER USER OF THE PROPERTY SHALL NOT IMPEDE THE FLOW OF

MAINTENANCE OF THE FACILITIES SHALL BE IN ACCORDANCE WITH THE FOLLOWING:

%SLOPE

MADE LAND GABBRO

AND DIABASE

MATERIALS

INDEX

NOT RATED NOT RATED

WATER DRAINING TO THE STORMWATER MANAGEMENT BASIN. 2. ALL ROOF DOWNSPOUTS, INLETS, CURB OPENINGS AND OTHER WATER WAYS SHALL BE KEPT OPEN AND

OPERATION TO PASS THE FLOW OF WATER TO THE BASIN AS INTENDED.

3. GRASS AND LANDSCAPING IN THE VICINITY OF ALL INLETS SHALL BE KEPT TRIM AND FREE FROM DEBRIS ACCUMULATION, AND DOWNSPOUTS AND INLETS SHALL BE KEPT FREE OF OBSTRUCTIONS THAT COULD BLOCK THE FREE FLOW OF WATER TO AND WITHIN THEM.

4. INLET SUMPS SHALL BE CLEANED OF ACCUMULATED DEBRIS BEFORE ANY DEBRIS CAN BE DISCHARGED INTO THE SYSTEMS. INLET STRUCTURES SHALL BE INSPECTED AT LEAST MONTHLY TO INSURE THAT THEY ARE CLEAN

5. SUBSURFACE PIPES SHALL BE INSPECTED ON AN ANNUAL BASIS TO INSURE THAT THEY ARE CLEAN AND OPERATIONAL. ANY ACCUMULATED DEBRIS AND SILT SHALL BE REMOVED IN A TIMELY MANER. THE SUBSURFACE PIPES SHALL BE KEPT FREE OF OBSTRUCTIONS THAT COULD BLOCK THE FREE FLOW OF WATER WITHIN THEM

6. PROMPT REMEDIAL MEASURES ARE TO BE TAKEN IN THE EVENT OF ANY BLOCKAGE OR MALFUNCTION OF

THE OWNER, OCCUPANT, TENANT OR OTHER USER OF THE PROPERTY SHALL NOT TAKE ANY MEASURES TO DISRUPT OR IN ANY WAY IMPAIR THE EFFECTIVENESS OF THE BASIN OR ITS CONTROLS. THIS INCLUDES ALTERATION OF GRADES IN ANY MANNER THAT WOULD DIVERT RUNOFF AWAY FROM INLET COLLECTION POINTS.

ERODIBILITY HYDROLOGIC AGRICULTURAL

GROUP CAPABILITY DRAINAGE

CLASS

TREES TO BE REMOVED:

8"DG TREE REPLACEMENT FORMULA: 6 - 18 INCH DBH REMOVED = 1 REPLACEMENT TREE = 3 REPLACEMENT TREES, 2 BEING LARGE CANOPY TREES 19 - 29 INCH DBH REMOVED = 6 REPLACEMENT TREES, 4 BEING LARGE CANOPY TREES 30 INCH DBH & GREATER REMOVED TOTAL TREES BEING REMOVED: 6 - 18 INCH DBH 19 - 29 INCH DBH 30 INCH DBH & GREATER


REPLACEMENT TREES REQUIRED SHOULD ANY ADDITIONAL TREES BE REMOVED, ADDITIONAL REPLACEMENT TREES SHALL BE PROVIDED IN

ACCORDANCE WITH THE RADNOR TOWNSHIP ORDINANCE No. 2012-05.

TREE REPLACEMENT NOTES: 1) REPLACEMENT TREES WILL BE SELECTED FROM THE LIST OF

TOWNSHIP APPROVED TREES PRIOR TO THE ISSUANCE OF A GRADING PERMIT. 2) TREES TO BE PLANTED OUTSIDE OF REQUIRED SITE LINE.

SOILS INFORMATION LOAD DEPTH DEPTH GRAVEL SAND ROADFILL TOPSOIL ROADS AND RESERVOIR EMBANKMENTS IRRIGATION SOURCE STREETS AREAS LAWNS DEVELOPMENT INDUSTRIAL LAGOONS | SEPTIC NOT NOT NOT RATED 6.6+ 6.6+ NOT NOT NOT NOT NOT NOT NOT STEED NOT RATED NO



LOCATION MAP SCALE: 1" = 600

1.) THE STORMWATER MANAGEMENT FACILITIES ARE DESIGNED FOR THE NEW AND/OR REPLACEMENT IMPERVIOUS COVER PROPOSED ON SITE OF 3,718 SF PLUS AN ADDITIONAL 7 SF TO ALLOW FOR POSSIBLE FUTURE DEVELOPMENT. IF THIS IMPERVIOUS COVER IS INSTALLED IN THE FUTURE, IT MAY BE DIRECTED TO THE STORMWATER MANAGEMENT SYSTEM.

2.) THE RESPONSIBILITY FOR THE CONTINUED MAINTENANCE AND OPERATION OF THE STORMWATER MANAGEMENT SYSTEM AND OTHER DRAINAGE FACILITIES SHALL BE THE OBLIGATION OF THE PROPERTY OWNER.

3.) THE TOWNSHIP ENGINEER'S OFFICE SHALL BE NOTIFIED 48 HOURS PRIOR TO THE CONSTRUCTION OF THE SEEPAGE BED AND PRIOR TO THE START OF EARTHMOVING ACTIVITIES.

4.) ON-SITE TREES ARE TO BE SAVED AND PRESERVED WHEREVER POSSIBLE 5.) ALL WOODY VEGETATION TO BE RETAINED WITHIN TWENTY-FIVE FEET OF A BUILDING SITE OR DISTURBED AREA SHALL BE PROTECTED FROM EQUIPMENT DAMAGE BY FENCING PLACED AT THE DRIPLINES.

SHALL BE MINIMIZED. TREATMENT OF THE TREES PRIOR TO CONSTRUCTION TO PROTECT THE ROOT SYSTEM SHALL BE PERFORMED. 7.) ALL DISTURBED ROOTS MUST BE CUT AS CLEANLY AS POSSIBLE. THE

6.) GRADE CHANGES AROUND THE DRIPLINES OF TREES TO BE RETAINED

TRENCH MUST BE BACKFILLED AS QUICKLY AS POSSIBLE, AVOIDING COMPACTION. TREE LIMBS MUST BE CUT BACK IN PROPORTION TO THE ROOT

8.) ON-SITE TREES TO BE SAVED SHALL BE PREPARED FOR CONSTRUCTION BY APPROPRIATE CROWN AND DEEP ROOTING FERTILIZATION AND PROTECTED BY APPROPRIATE FENCING.

PERCOLATION TEST:

NOTES:

DELAWARE VALLEY SEPTICS INC. PERFORMED STORM WATER INFILTRATION TESTING ON SITE ON JULY 6, 2015. THE AVERAGE PERCOLATION RATE FOUND DURING TESTING WAS 3.0 IN/HR.

CARE OF EXISTING TREES:

DURATION OF PROJECT.

OF TRUNK DIAMETER.

ALL WOODY VEGETATION TO BE RETAINED WITHIN

TWENTY-FIVE FEET OF A BUILDING SITE OR DISTURBED

FENCING PLACED AT THE DRIPLINES. TREE PROTECTION

TREES FROM DAMAGE DUE TO LANDSCAPE OPERATIONS,

OTHERS. MAINTAIN PROTECTION FENCING FOR THE

FENCING SHALL BE INSTALLED TO PROTECT ALL EXISTING

OPERATIONS BY OTHER CONTRACTORS AND TRADES, AND

GRADE CHANGES AROUND THE DRIPLINES OF TREES TO BE

PRIOR TO CONSTRUCTION TO PROTECT THE ROOT SYSTEM

SELECTIVELY PRUNE EXISTING TREES AT THE EDGE OF ALL

ARCHITECT'S DIRECTION. REMOVE SUCKER SHOOTS, DEAD,

DISTURBED ROOTS MUST BE CUT AS CLEANLY AS POSSIBLE

POSSIBLE, AVOIDING COMPACTION. TREE LIMBS MUST BE

TREE PROTECTION ZONES, AND OTHER EXISTING TREES

ANY EXCAVATION NEAR ADJACENT ROOT SYSTEMS WILL

REQUIRE ROOT PRUNING OF AFFECTED TREE(S). ALL

THE TRENCH MUST BE BACKFILLED AS QUICKLY AS

CUT BACK IN PROPORTION TO THE ROOT AREA LOSS.

6. FERTILIZE IN EARLY SPRING BEFORE GROWTH BEGINS.

SUBJECT TO LANDSCAPE ARCHITECT'S APPROVAL.

FERTILIZE PRUNED EXISTING TREES WITH 3 TO 4 LBS. OF

LIQUID FERTILIZER PER 1,000 SQUARE FEET OF DRIP AREA,

OR, 5 GALLONS OF LIQUID FERTILIZER PER CALIPER INCH

FERTILIZE BEGINNING 2' FROM TRUNK AT INTERVALS 2' TO

3' ON CENTER IN A GRID-LIKE PATTERN TO A DEPTH OF

INJECTION FERTILIZATION METHOD SHALL BE ACCEPTABLE

6-18" WITHIN THE DRIPLINE AND BEYOND WHERE POSSIBLE.

AFFECTED BY CONSTRUCTION, UNDER LANDSCAPE

RUBBING AND DAMAGED BRANCHES.

RETAINED SHALL BE MINIMIZED. TREATMENT OF THE TREES

AREA SHALL BE PROTECTED FROM EQUIPMENT DAMAGE BY

ZONING DISTRICT R-1 (RESIDENCE DISTRICT)

LOT AREA	I ACKE MIN.
LOT WIDTH	120' FEET MIN. AT BUILDING LINE
BLDG. AREA	15% MAX.
FRONT YARD	60 FEET MIN.
SIDE YARD	60 FEET AGG. (25 FEET MIN.)
REAR YARD	40 FEET MIN.
HEIGHT	35 FEET MAX.
IMPERVIOUS SURFACE	22% MAX.
RIPARIAN BUFFER	35 FEET MIN.
ACCESSORY USE SETBACK:	10 FEET MIN.

FOR MORE DETAILED INFORMATION YOUR ATTENTION IS CALLED TO THE ZONING CODE OF RADNOR TOWNSHIP, LATEST EDITION.

LOT DATA: LOT AREA = 23,216 S.F. (0.533 ACRES)

SOURCE OF TITLE: DEED BOOK 5560 PAGE 2391 411 LOUELLA AVENUE WAYNE, PA 19087 TMP No. 36-03-01736-00 Block No. 21 Unit No. 72

EXISTING IMPERVIOUS COVERAGE:

RESIDENCE	1,200	٠.١.	
GARAGE	388	S.F.	
DRIVEWAY	2,140	S.F.	
DECK	343	S.F.	
WALLS	163	S.F.	
WALKS/STEPS	961	S.F.	
TOTAL	5,293	S.F.	(22.80%)

IMPERVIOUS TO BE REMOVED:

PORTION OF RESIDENCE	<u>23</u> 4	
GARAGE	388	:
DRIVEWAY	486	
DECK	343	
WALLS	86	
WALKS/STEPS	874	

IMPERVIOUS COVERAGE TO BE ADDED:

RESIDENCE	1,648	S.F
PORCH	126	S.F
DRIVEWAY	1,331	S.F
BILCO	36	S.F
DECK	48	S.F
PATIO	483	S.F
WALLS	46	S.F
TOTAL	3,718	S.F

PROPOSED IMPERVIOUS COVERAGE:

RESIDENCE	2,712	S.F.	
PORCH	126	S.F.	
DRIVEWAY	2,985	S.F.	
BILCO	36	S.F.	
DECK	48	S.F.	
PATIO	483	S.F.	
WALLS	123	S.F.	
WALKS/STEPS	87	<u>S.F.</u>	
TOTAL	6,600	S.F.	(28.43

1,307 S.F.

OPERATION AND MAINTENANCE NOTES:

1. THE RESPONSIBILTY FOR THE CONTINUED MAINTENANCE AND OPERATION OF THE STORMWATER MANAGEMENT SYSTEM AND OTHER DRAINAGE FACILITIES SHALL BE THE OBLIGATION OF THE PROPERTY OWNER.

INFILTRATION BMP NOTES:

NET INCREASE


1) INFILTRATION BMP FILTER FABRIC AND STONE SHOULD BE KEPT CLEAN OF SOIL/SEDIMENT DURING THE INSTALLATION PROCESS. IF INSPECTION INDICATES THAT SOIL SEDIMENT HAS ENTERED ANY OF THE INFILTRATION SEEPAGE BEDS, APPROPRIATE MEASURES (i.e. CLEANING THE SOIL/SEDIMENT FROM FABRIC, STONE, BED ETC. AND OR REPLACEMENT OF THE FABRIC AND STONE) SHOULD BE ADDRESSED.

2) ALL STONE FOR THE CONSTRUCTION OF THE INFILTRATION BMP SHOULD BE UNIFORMLY GRADED AND CLEAN WASHED AGGREGATE.


3) THE BOTTOM OF ALL INFILTRATION BMPs SHALL BE UNDISTURBED OR UNCOMPACTED SUBGRADE.

4) INFLOW AND OUTFLOW POINTS INTO THE INDIVIDUAL ON-LOT SYSTEM SHOULD BE KEPT CLEAR OF LEAVES AND OTHER DEBRIS. ANY LEAVES AND DEBRIS WILL NEGATIVELY IMPACT THE PERFORMANCE OF THE SYSTEM. ALL DOWNSPOUTS AND OVERFLOW PIPES SHOULD BE KEPT IN GOOD WORKING ORDER.

5) AFTER THE INFILTRATION BED IS COMPLETELY INSTALLED, ALL HEAVY CONSTRUCTION EQUIPMENT SHALL BE RESTRICTED FROM THE INFILTRATION BEDS TO ELIMINATE IMPACTS WHICH MAY COMPROMISE IT. IN THE EVENT ANY IMPACTS COMPROMISE THE FUNCTIONALITY OF THE INFILTRATION BEDS, IT MUST BE IMMEDIATELY REPAIRED OR REPLACED TO DESIGN SPECIFICATIONS.








S C

O



DATE: JULY 9, 2015 SHEET NO. OF 4

SCALE: 1" = 20'FILE NO.: 15-155

EXCAVATION. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO THE START OF ANY CONSTRUCTION.

SLOPES 20%

AND GREATER

ALL LOCATIONS SHOULD BE CONSIDERED APPROXIMATE.

FACILITIES BEFORE THE START OF ANY WORK.

ALL LOCATIONS OF EXISTING UTILITIES, SHOWN ON THIS PLAN, HAVE

BEEN DEVELOPED FROM FIELD LOCATIONS OF VISIBLE ABOVE GROUND

UTILITY STRUCTURES AND INFORMATION FURNISHED BY THE UTILITY

COMPLETENESS OR ACCURACY OF THE LOCATIONS AND DEPTH OF ALL

STRUCTURES CANNOT BE GUARANTEED. CONTRACTORS MUST VERIFY

ALL LOCATIONS AND DEPTHS OF ALL UNDERGROUND UTILITIES AND

AS PER ACT 187 HOUSE BILL 2627, BEFORE THE START OF ANY

-800-242-1776 THREE DAYS PRIOR TO THE START OF ANY

EXCAVATION WORK THE CONTRACTOR SHALL NOTIFY THE AFFECTED

UTILITY COMPANIES THROUGH THE PENNSYLVANIA "ONE CALL SYSTEM"

OVERHEAD ELECTRIC

ELECTRIC LINE

EXISTING STORM PIPES

427.25 X PROPOSED SPOT ELEVATION

PERC TEST LOCATION

NEW BUILDING AREA

NEW PATIOS / WALKS

NEW RETAINING WALLS

NEW DRIVEWAY AREAS

SLOPES

14%TO 20%

- GAS LINE

— WATER LINE

_____ EXISTING 1' CONTOUR

______ EXISTING 5' CONTOUR

— SANITARY LINE

ERODIBILITY HYDROLOGIC AGRICULTURAL

GROUP

CAPABILITY

CLASS

DRAINAGE

DRAINED

BEARING TO SH TO

NOT RATED 6.6+ 6.6+

%SLOPE

INDEX

|NOT RATED|NOT RATED|


GEOTEXTILE FABRIC EXISITNG GROUND STONE PLAN VIEW PROVIDE APPROPRIATE TRANSITION BETWEEN STABILIZED CONSTRUCTION ENTRANCE AND PUBLIC RIGHT OF WAY

STABILIZED CONSTRUCTION ENTRANCE

1. THICKNESS - NOT LESS THAN EIGHT (8) INCHES. WIDTH - NOT LESS THAN FULL WIDTH OF ALL

WASHING — WHEN NECESSARY, WHEELS SHALL BE CLEANED TO E CLEANED TO REMOVED SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT

MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A



SOILS INFORMATION

DEPTH DEPTH GRAVEL SAND ROADFILL TOPSOIL LOCAL FUND ROADS AND RESERVOIR EMBANKMENTS IRRIGATION

NOT

NOT

RATED RATED RATED RATED

STREETS

AREAS

FILTER FABRIC FENCE MUST BE PLACED AT LEVEL GRADE. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8' UP SLOPE AT 45" TO THE MAIN BARRIER ALIGNMENT. ANY SILT FENCING WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE REPLACED WITH ROCK FILTER OUTLETS IMMEDIATELY. SEE ROCK FILTER OUTLET DETAIL. SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT THE FENCE.

<u>STANDARD FILTER FABRIC FENCE</u>

NOT RATEDINOT RATED NOT RATED NOT RATED NOT RATEDINOT RA

RESIDENTIAL LIGHT | SEWAGE | ON-SITE

|DEVELOPMENT |INDUSTRIAL | LAGOONS | SEPTIC

HYDROSEEDING SPECIFICATIONS

1 TON

3 TONS

DEFINITION: STABILIZING SEDIMENT PRODUCING AND SEVERELY ERODED AREAS BY ESTABLISHING PERMANENT GRASS

PURPOSE: TO PROVIDE PERMANENT VEGETATIVE COVER TO CONTROL RAPID RUN-OFF AND EROSION.

PROCEDURE: SURFACE TO BE HYDRO-SEEDED SHALL BE CLEANED OF ALL DEBRIS AND OTHER MATTER HARMFUL TO UNIFORM

GERMINATES. A WATER-SLURRY MIXTURE COMPOSED OF THE BELOW MENTIONED "MATERIALS" SHALL BE SPRAYED UNIFORMLY OVER THE AREAS TO BE HYDRO-SEEDED. APPLICATION RATE MATERIALS:

PERMANENT SEEDING

DESCRIPTION (PER ACRE) 60% PENNSTAR KENTUCKY BLUEGRASS 260 LBS. SÉED MIXTURE 30% PENNLAWN RED RESCUE 10% PENNFINE PERRENIAL RYEGRASS % BY WEIGHT 1,000 LBS. 10-20-20 COMMERCIAL FERTILIZER GROUND AGRICULTURAL LIMESTONE 2 TONS (MAY BE APPLIED SEPARATELY) HAY OR STRAW 3 TONS MULCH TERRA TACK OR EQUIVLANT 20 LBS. SÓIL STABILIZER TEMPORARY ANNUAL RYEGRASS (95% PURE) 40 LBS. SÉED 1,000 LBS.

5-5-5

GROUND AGRICULTURAL LIMESTONE


(MAY BE APPLIED SEPARATELY)

HAY OR STRAW

POINTS OF INGRESS OR EGRESS.

BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE THROUGH USE OF SAND BAGS, GRAVEL, BOARDS OR OTHER APPROVED METHODS

CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHTS—OF—WAY MUST BE REMOVED IMMEDIATELY.



1) NEWLY GRADED SLOPES TWENTY FIVE PERCENT (25% OR GREATER) SHALL BE SODDED OR STABILIZED WITH EROSION CONTROL NETTING.

2) GEOTEXTILE FABRIC SHALL BE CLASS 1. GEOTEXTILE FABRIC IN ACCORDANCE WITH PENNDOT SPECIFICATION FROM 408. THE TYPE AND/OR THICKNESS SHALL BE DUPONT TYPAR #3401, AMOCO PROPEX #4545 OR APPROVED EQUAL OR AS OTHERWISE INDICATED ON THE PLAN.

3) TO ALL AREA WHICH REMAIN DISTURBED FOR MORE THAN 4 DAYS AND WILL BE SUBJECT TO THE ACTION OF EARTHMOVING AND OTHER EQUIPMENT, APPLY A MULCH (WOODCHIP-20 TONS PER ACRE; HAY OR STRAW-3 TONS PER ACRE). ALL OTHER DISTURBED AREAS REMAINING OPEN FOR MORE

4) ALL TREES AND BRUSH WITHIN THE SIGHT TRIANGLE SHALL BE TRIMMED AND/OR REMOVED AS NECESSARY TO OBTAIN CLEAR SIGHT DISTANCE WITH THE APPROVAL OF THE TOWNSHIP ARBORIST.

THAN 4 DAYS SHALL BE TEMPORARILY SEEDED AND MULCHED.

5) SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF/AND OR SEDIMENT DISPLACEMENT. STOCKPILES OF WOODCHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.

6) THE CONTRACTOR SHALL, BY SCHEDULING THE CONSTRUCTION, UTILIZE NEW PLANTINGS AND PROPERLY INSTALL EROSION CONTROL FENCING, HAY BALES AND OTHER EROSION CONTROL MEASURES TO MINIMIZE EROSION

7) ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 4 DAYS MUST BE SEEDED AND MULCHED IMMEDIATELY. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE RECOMMENDED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURED WITHIN ONE YEAR MAY BE SEEDED AND MULCHED WITH A QUICK GROWING TEMPORARY SEEDING MIXTURE AND MULCH. DISTURBED AREAS WHICH ARE EITHER AT FINISHED GRADE OR WILL NOT BE REDISTURED WITHIN ONE YEAR MUST BE SEEDED AND MULCHED WITH A PERMANENT SEED MIXTURE AND MULCH. DIVERSIONS, CHANNELS, SEDIMENTATION BASINS, SEDIMENT TRAPS, AND STOCKPILES MUST BE SEEDED AND MULCHED IMMEDIATELY.

8) A ROUTINE "END-OF-DAY-CHECK" SHALL BE MADE DURING CONSTRUCTION TO MAKE SURE THAT ALL CONTROL MEASURES ARE WORKING PROPERLY. ALL PERSONS ENGAGED IN LAND DISTURBANCE ACTIVITIES SHALL DESIGN. IMPLEMENT. AND MAINTAIN CONTROL MEASURES WHICH PREVENT ACCELERATED EROSION AND SEDIMENTATION. THERE SHALL BE NO ADVERSE DISCHARGE OF THE SEDIMENT OR OTHER SOLID MATERIALS FROM THE SITE AS THE RESULT OF STORMWATER RUNOFF.

9) TEMPORARY EROSION CONTROL MEASURES MAY BE REMOVED ONLY AFTER THE CONSTRUCTION AREA AND CONTAINED SILT IS STABILIZED AND THE LAWN AREA ESTABLISHED.

MAINTENANCE OF TEMPORARY SEDIMENTATION CONTROL STRUCTURES

STABILIZED CONSTRUCTION ENTRANCE: THE STABILIZED CONSTRUCTION ENTRANCES ARE TO BE CONSTRUCTED PER THE DETAIL. THE STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED SO THAT TIRE SCRUBBING ACTIVITY DOES NOT BECOME INEFFECTIVE. ANY BUILDUP OF MUD OR SOIL ON THE STREET SHALL BE CLEANED AT THE END OF EACH WORKING DAY.

INLET SILT TRAPS: INLET SILT TRAPS SHALL BE CONSTRUCTED PER THE DETAIL AND CLEANED AFTER EACH STORM EVENT OR AS DIRECTED BY THE CONSERVATION DISTRICT OR TOWNSHIP ENGINEER.

SILT FENCE: SILT FENCE SHALL BE INSTALLED PER THE DETAIL WITH ROCK FILTER OUTLETS PROVIDED EVERY 100 FEET AND AT EXISTING AND GRADED LOW POINTS. SEDIMENT SHALL BE REMOVED FROM SILT FENCES WHEN IT REACHES 1/2 THE FENCE HEIGHT OR AS DIRECTED BY THE CONSERVATION DISTRICT OR TOWNSHIP ENGINEER. SILT FENCING WHICH AS BEEN UNDERMINED OR TOPPED WILL BE REPLACED WITH ROCK FILTER OUTLETS IMMEDIATELY.

SEDIMENT DISPOSAL: SILT REMOVED FROM TEMPORARY SEDIMENT CONTROL STRUCTURES SHALL BE DISPOSED OF ON-SITE IN LANDSCAPED AREAS LOCATED OUTSIDE OF FLOOD PLAINS, WETLANDS, STEEP SLOPES AND DRAINAGE SWALES.

DUST CONTROL: DUST AND OTHER PARTICULATES SHALL BE KEPT WITHIN TOLERABLE LIMITS BY USING WATER. APPLICATION SHALL CONSERVATION DISTRICT.

PLACING TOPSOIL OR TOPSOIL MIXTURE

PREPARATION OF AREAS TO BE TOPSOILED

GRADE THE AREAS TO BE COVERED BY TOPSOIL. USING ACCEPTABLE METHODS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE PLACING THE TOPSOIL. REMOVE STONES AND OTHER FOREIGN MATERIAL 2 INCHES OR LARGER IN DIMENSION. REMOVE AND SATISFACTORILY DISPOSE OF UNSUITABLE AND SURPLUS MATERIAL.

PLACING AND SPREADING TOPSOIL

PLACE TOPSOIL ON THE PREPARED AREAS AND, UNLESS OTHERWISE INDICATED, SPREAD AND COMPACT TO A 4-INCH UNIFORM DEPTH ± 1 1/2 INCHES. COMPACT WITH A ROLLER WEIGHING NOT OVER 120 POUNDS PER FOOT WIDTH OF ROLLER OR BY OTHER ACCEPTABLE METHODS, AS DIRECTED. REMOVE OVERDEPTH TOPSOIL, UNLESS OTHERWISE AGREED UPON IN WRITING. DO NOT PLACE TOPSOIL IN A WET OR FROZEN CONDITION.

SEEDING SPECIFICATIONS:

WHERE DENUDED AREAS ARE DESIRED TO BE LAWN:

PERFORM ALL CULTURAL OPERATION AT RIGHT ANGLES TO THE

2.APPLY LIME ACCORDING TO TEST OR AT THE RATE OF 25 LBS. OF GROUND LIMESTONE PER 1,000 SQ. FT.


APPLY FERTILIZER ACCORDING TO SOIL TEST OR WORK IN DEEPLY 20 LBS. OF 0-20-20 OR EQUIVALENT PER 1,000 SQ. FT. AND AT THE TIME OF SEEDING. WORK INTO THE SURFACE 10 LBS. OF 10-10-10 OR EQUIVALENT PER 1,000 SQ. FT. OR OTHER APPROVED MIXTURE.

4. SMOOTH AND FIRM SEEDED PRIOR TO SEEDING.

SEED USING A MIXTURE OF 60% PENNSTAR KENTUCKY BLUEGRASS, 30% PENNLAWN RED FESCUE AND 10% PENNFINE PERENNIAL RYEGRASS AT THE RATE OF FIVE (5) POUNDS PER 1,000 SQ. FT. OR OTHER APPROVED MIXTURE.

6. COVER GRASS AND LEGUME SEEDS WITH 1/4" OF SOIL WITH SOIL EQUIPMENT, MULCH, USING 2 BALES/1,000 SQ. FT.

WHERE SLOPES EXCEED 25% JUTE NETTING OR OTHER APPROVED (EQUAL) SLOPE STABILIZATION MEASURES SHALL BE UTILIZED. IN ÀDDITION, THE SEEDING SPECIFICATIONS FOR STEEP SLOPES SHALL BE INCREASED TO INCLUDE 3 LBS/1,000 SQ. FT. OF ANNUAL RYEGRASS FOR RAPID VEGETAL ESTABLISHMENT.



GRAVEL SEDIMENT FILTER FOR INLET

CONSTRUCTION TIMING AND SEQUENCE

NOTE: THE TOWNSHIP ENGINEER SHALL BE NOTIFIED 48 HOURS PRIOR TO THE INSTALLATION OF THE SEEPAGE BED AND PRIOR TO THE START OF ANY EARTHMOVING ACTIVITIES.

01. NOTIFY THE TOWNSHIP THAT CONSTRUCTION IS GOING TO COMMENCE. ANTICIPATED DATE: AUGUST 2015.

02. THE EXISTING DRIVE IS TO BE UTILIZED FOR CONSTRUCTION ACCESS. PROVIDE A HOSE TO CLEAN TIRES TO PREVENT SEDIMENT FROM BEING TRACKED OFF SITE INTO PUBLIC ROADWAYS. IN THE EVENT THAT SEDIMENT CANNOT BE KEPT OFF OF TOWNSHIP ROADWAYS A STABILIZED CONSTRUCTION ENTRANCE SHALL BE PROVIDED. ALL CONSTRUCTION VEHICLES ENTERING/EXITING THE SITE MUST USE THIS ENTRANCE.

03. INSTALL TREE PROTECTION AS INDICATED ON THE PLAN.

04. INSTALL SILT FENCE AS SHOWN ON THE PLAN AND ON THE DOWNHILL SLOPE OF ANY EXCAVATION OR ANTICIPATED DISTURBANCE.

05. PRIOR TO EARTH DISTURBANCE, NOTIFY THE TOWNSHIP ENGINEER THAT

CONSTRUCTION IS GOING TO BEGIN. 06. ONCE THE EROSION AND SEDIMENT CONTROLS ARE IN PLACE AND FUNCTIONING, BEGIN DEMOLITION OF THE PORTIONS OF THE RESIDENCE, GARAGE. AND THE OTHER IMPERVIOUS FEATURES DESIGNATED FOR REMOVAL. ALL CONSTRUCTION DEBRIS SHALL BE REMOVED FROM THE SITE AND

DISPOSED OF IN AN APPROVED MANNER. 07. CLEAR AND GRUB THE AREAS AS NECESSARY WITHIN THE LIMITS OF DISTURBANCE OF EXISTING VEGETATION. STRIP TOPSOIL FROM AREAS OF CONSTRUCTION AND STOCKPILE SUITABLE MATERIAL FOR FUTURE USE. UNSUITABLE MATERIAL SHALL BE DISPOSED OF PROPERLY. SURROUND

TOPSOIL WITH SILT FENCE AND SEED TO ESTABLISH TEMPORARY VEGETATIVE 08. EXCAVATE FOR AND BEGIN TO CONSTRUCT THE FOUNDATIONS FOR THE NEW BUILDING ADDITION. UPON COMPLETION OF FOUNDATION WALLS, BACKFILL FOUNDATIONS AND ROUGH GRADE AROUND THE HOUSE. ANY GRADED OR DISTURBED AREA MUST BE TEMPORARILY SEEDED IF NO FURTHER

EARTH MOVING IS ANTICIPATED IMMEDIATELY. USE ANY ADDITIONAL EXCAVATED MATERIAL FROM THE NEW FOUNDATION TO BACKFILL THE EXISTING BASEMENT. 09. CONTINUE WITH BUILDING CONSTRUCTION AND ROUGH GRADE THE SITE.

INSTALL UTILITIES AS NECESSARY. 10. CONCURRENT WITH THE BUILDING CONSTRUCTION INSTALL THE ROOF

11. PLACE STONE BASE FOR NEW DRIVEWAY AREAS. BEGIN TO CONSTRUCT

12. INSPECT SEDIMENT BARRIERS FREQUENTLY, ESPECIALLY AFTER HEAVY

FROM THE TOWNSHIP ENGINEER, INSTALL PERMANENT STORMWATER MANAGEMENT SYSTEM, AND LEVEL SPREADER. CONNECT THE ROOF DRAINS AND INLET TO THE SYSTEM, AND CONNECT THE SYSTEM TO THE LEVEL SPREADER. THE TOWNSHIP ENGINEER SHALL BE NOTIFIED 48 HOURS PRIOR


14. INSTALL FINAL TOP COURSES ON THE NEW DRIVEWAY AREAS.

GRADED AREAS TO REESTABLISH PERMANENT VEGETATION. STABILIZE SLOPES IN EXCESS OF 4:1 WITH SOD OR EROSION CONTROL NETTING AND MULCH. 16. INSTALL FINAL LANDSCAPE FEATURES, AND COMPLETE CONSTRUCTION. 17. UPON PERMANENT STABILIZATION, REMOVE THE SEDIMENT BARRIERS.

15. FINAL GRADE DENUDED AREAS, SPREAD STOCKPILED TOPSOIL AND SEED

18. CONSTRUCTION COMPLETED. ANTICIPATED DATE: APRIL 2016.


Hi-Velocity Curlex Blankets



duty extruded plastic mesh netting designed o last for vears and reinforce the root system after the excelsior mat has decomposed. The are smolder—resistant—no chemical additives. STAPLING INSTRUCTIONS FOR AMXCO HI-VELOCITY CURLEX BLANKETS
Use wire staples, .091" in diameter or greater, U" shaped with legs 8" long or longer and
" to 2" crown. Size and gauge of staples

used will vary with soil types. Use four staples across at the start of each roll and continu intervals. When blankets are placed along— side of each other, staple so as to catch the edge of each roll. In addition to stapling the edges of the blanket at the appropriate intervals (see drawing), place staples in the center of the blanket halfway between the outer staples.

CHANNEL STABILIZATION



. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.

2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP X 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE.

4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" OVERLAP. 5. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART. DATE: JULY 9, 2015 SHEET NO. OF 4 SCALE: 1" = 20'FILE NO.: 15-155

S C

CIATES, AND SURVE

ASSOC AND LA

2 MAX

SYMBOL

MADE LAND GABBR

AND DIABASE

MATERIALS

TOP SOIL

TYPICAL SOIL STOCKPILE CROSS SECTION

TOP SOIL PROTECTION:

OR USED AS FILL. TOPSOIL SHALL BE REMOVED FROM THE AREAS OF

CONSTRUCTION AND STORED SEPARATELY THE TOPSOIL SHALL BE

COMPLETION OF CONSTRUCTION, THE TOPSOIL SHALL BE UNIFORMLY

STABILIZED TO MINIMIZE EROSION DURING STORAGE. UPON

LL LOCATIONS OF EXISTING UTILITIES, SHOWN ON THIS PLAN, HAVE BEEN DEVELOPED FROM FIELD LOCATIONS OF VISIBLE ABOVE GROUND UTILITY STRUCTURES AND INFORMATION FURNISHED BY THE UTILITY

COMPLETENESS OR ACCURACY OF THE LOCATIONS AND DEPTH OF ALL

STRUCTURES CANNOT BE GUARANTEED. CONTRACTORS MUST VERIFY

ALL LOCATIONS AND DEPTHS OF ALL UNDERGROUND UTILITIES AND

AS PER ACT 187 HOUSE BILL 2627, BEFORE THE START OF ANY

-800-242-1776 THREE DAYS PRIOR TO THE START OF ANY

EXCAVATION WORK THE CONTRACTOR SHALL NOTIFY THE AFFECTED JTILITY COMPANIES THROUGH THE PENNSYLVANIA "ONE CALL SYSTEM"

EXCAVATION. THE CONTRACTOR SHALL VERIFY THE LOCATION AND

DEPTH OF ALL UTILITIES PRIOR TO THE START OF ANY CONSTRUCTION.

ALL LOCATIONS SHOULD BE CONSIDERED APPROXIMATE.

FACILITIES BEFORE THE START OF ANY WORK.

TOPSOIL SHALL NOT BE REMOVED FROM THE DEVELOPMENT SITE

NOTE: SILT FENCE MUST COMPLETELY ENCIRCLE STOCKPILES

REDISTRIBUTED ON THE SITE.

RAINWATER COLLECTION SYSTEM, INLET, AND CONVEYANCE PIPING. PLACE INLET PROTECTION ON THE INLET. OTHER SITE IMPROVEMENTS. STORMS. REPLACE AND REPAIR SEDIMENT BARRIERS AS NECESSARY. 13. UPON FINAL STABILIZATION OF THE CONTRIBUTORY AREA AND APPROVAL TO THE INFILTRATION OF THE STORMWATER MANAGEMENT SYSTEM.

IMMEDIATELY SEED ANY DENUDED AREAS DUE TO THEIR REMOVAL.


American Excelsior Company Designed to control erosion in areas of high-velocity water runoff, the Excelsior Hi-Velocity Curlex Blanket is a machine-produced mat of longer fiber length, with consistent thickness and fiber evenly distributed over its entire area.


INSTALLATION INSTRUCTIONS This blanket is designed to withstand high-velocity water movements in ditches and on slopes. In ditches, unroll blanket in direction of water flow. When using two blankets side by side in a ditch, do not put the seems in the center of the ditch. Offset 6" to 1 foot. On slopes, start blanket 3 feet over crest of slope or dig anchor ditches if specified. Blankets may be installed horizontally or vertically, whichever is easier.

Hi-Velocity Curlex Blankets are recommended for the following water velocities: VELOCITY/FEET SOIL TYPES PER SÉCOND Clay, clay loam, silty clay...... Clay,silty clay, sandy clay loam....9.8 FPS Fine sandy loam sity loam.....8.6 FPS These figures are based on ditch lining at over 3% grade up to 13% on slope protection, the determining factor would be the grade of the, berms above and

Typical Stapling Pattern for High—Velocity Ditches and Use 4 staples across at the start of each roll and continue to staple throughout the length of the roll at 2 ft. intervals.

sheeting effect of water velocity.





STORMWATER MANAGEMENT SYSTEM #1

CONSTRUCTION SPECIFICATIONS FOR STORMWATER MANAGEMENT SYSTEMS REQUIRED GRADES AND SECTIONS AS SHOWN IN THE DRAWINGS. THE TYPE OF EQUIPMENT USED IN SUBGRADE PREPARATION CONSTRUCTION SHALL NOT CAUSE UNDUE SUBGRADE COMPACTION. TRAFFIC OVER SUBGRADE SHALL BE KEPT AT A MINIMUM. 3. INSTALL POLYPROPYLENE NONWOVEN GEOTEXTILE FABRIC WHICH MEETS PADOT CLASS 1 SPECIFICATIONS (I.E., DUPONT TYPAR #3401, AMOCO PROPEX #4545, OR APPROVED EQUAL) ON BOTTOM OF BED AREAS AND TACK UP SIDES OF EXCAVATION. WHERE EDGES OF ROLLS OVERLAP, THEY SHALL DO SO BY AT LEAST EIGHTEEN INCHES. ADEQUATE FABRIC SHALL BE LEFT ON THE ROLLS (NOT CUT FROM SIDE INSTALLATION) TO FACILITATE OVERTOPPING THE SYSTEM AT COMPLETION OF INSTALLATION. 4. ALL STONE FOR THE CONSTRUCTION OF THE INFILTRATION BMP SHALL BE

UNIFORMLY GRADED AND CLEAN, WASHED, AGGREGATE. THE STONE SHALL MEET PENNDOT/AASHTO #1 SPECIFICATIONS. STONE TO BE CHECKED BY THE DESIGN OR SITE ENGINEER PRIOR TO INSTALLATION. STONE BASE COURSE SHALL BE LAID OVER A DRY SUBGRADE TO A DEPTH SHOWN IN DRAWINGS. DO NOT ROLL OR COMPACT THE STONE BASE COURSE. KEEP THE BASE COURSE CLEAN FROM DEBRIS, CLAY AND ERODING SOIL. INSTALL TANKS AND PIPE AS SHOWN AND BACKFILL WITH STONE. 6. COVER SYSTEM WITH REMAINING FABRIC, ALLOWING OPENINGS FOR ACCESS

COVERS. 7. SYSTEM TO BE TOTALLY ENCLOSED IN THE NON-WOVEN GEOTEXTILE FABRIC. 8. INFILTRATION BMP FILTER FABRIC AND STONE SHOULD BE KEPT CLEAN OF SOIL/SEDIMENT DURING THE INSTALLATION PROCESS. IF INSPECTION INDICATES THAT SOIL SEDIMENT HAS ENTERED ANY OF THE INFILTRATION SEEPAGE BEDS, APPROPRIATE MEASURES (i.e. CLEANING THE SOIL/SEDIMENT FROM FABRIC, STONE, BED ETC. AND OR

9. THE BOTTOM OF ALL INFILTRATION BMP'S SHALL BE UNDISTURBED OR UNCOMPACTED SUBGRADE. 10. INFLOW AND OUTFLOW POINTS INTO THE INDIVIDUAL ON-LOT SYSTEMS SHOULD BE KEPT CLEAR OF LEAVES AND OTHER DEBRIS. ANY LEAVES OR DEBRIS WILL NEGATIVELY IMPACT THE PERFORMANCE OF THESES SYSTEMS. ALL DOWNSPOUTS AND OVERFLOW PIPES SHOULD BE KEPT IN GOOD WORKING ORDER. 11. SEEPAGE BEDS SHALL NOT RECEIVE RUNOFF UNTIL THE ENTIRE DRAINAGE AREA CONTRIBUTING TO THE INFILTRATION BMP HAS ACHIEVED FINAL STABILIZATION.


1. GEOTEXTILE FABRIC SHALL BE CLEAN NON-WOVEN GEOTEXTILE (PERMEABLE FILTER FABRIC) CLASS 1 AND SHALL BE IN ACCORDANCE WITH PADOT SPECIFICATION FROM 40B. THE TYPE AND/OR THICKNESS SHALL BE DUPONT TYPAR #3401, AMOCO PROPEX #4545 OR APPROVED EQUAL OR AS OTHERWISE INDICATED ON THE PLAN." 2. ALL STONE USED FOR THE CONSTRUCTION OF THE INFILTRATION BMP SHALL BE UNIFORMLY GRADED, CLEAN, AND WASHED CRUSHED STONE AGGREGATE MEETING PENNDOT/AASHTO #1 SPECIFICATIONS. 3. ALL PERSONS ENTERING ACTIVE TANKS, MANHOLES, INLETS, ETC. MUST COMPLY WITH OSHA REQUIREMENTS FOR ENTRY INTO CONFINED 4. RAIN WATER CONDUCTORS ARE TO COLLECT ALL ROOF RUNOFF AND


REPLACEMENT OF THE FABRIC AND STONE) SHOULD BE ADDRESSED.

CONVEY IT TO THE APPROPRIATE STORMWATER MANAGEMENT FACILITY. 5. CLEANOUTS ARE REQUIRED AT ALL CHANGES IN DIRECTION OF THE ROOF DRAINS AND SANITARY SEWER LATERALS. 6. ALL SEEPAGE BEDS SHALL BE INSTALLED WITH A MINIMUM SEPARATION DISTANCE OF 10 FEET FROM ALL BASEMENT WALLS. ALL CMP AND HCMP SHALL BE ALUMINUM OR ALUMINIZED STEEL. 8. ALL HDPE PIPE SHALL BE SMOOTH INTERIOR FLOW.


9. ALL PVC PIPE SHALL BE SDR 35. 10. ALL INLETS SHALL BE INSTALLED WITH A TWELVE (12") INCH SUMP

CONDITION IN ORDER TO IMPROVE THE EFFICIENCY OF THE RUNOFF COLLECTION. 11. THE RISER CONNECTIONS IN THE STORMWATER MANAGEMENT SYSTEM SHALL BE WATERTIGHT. REFER TO DETAILS. 12. WHERE DRAINAGE SWALES ARE WITHIN 20' OF A BASEMENT, WATERPROOFING SHALL BE APPLIED TO THE BASEMENT. 13. PERFORATIONS FOR 48" CMP SHALL SATISFY AASHTO DESIGNATION M36/M 36M-90 FOR CLASS 2 PERFORATIONS. THE PERFORATIONS SHALL BE CIRCULAR HOLES WITH NOMINAL DIAMETERS OF 5/16 TO 3/8 INCH. THE PERFORATIONS SHALL BE UNIFORMLY SPACED AROUND THE FULL PERIPHERY OF THE PIPE. THE PERFORATIONS SHALL PROVIDE AN OPENING AREA OF NOT LESS THAN 3.3 SQ. IN. PER SQ. FT. OF PIPE SURFACE BASED ON NOMINAL DIAMETER AND LENGTH OF PIPE. 30 PERFORATIONS, 3/8 INCH DIAMETER, PER SQUARE FOOT OR 566 PERFORATIONS PER LINEAR FOOT SATISFIES THIS REQUIREMENT.






NDS ROUND GRATE WITH SEWER & DRAIN ELBOW NOT TO SCALE



N. T. S.



INC

ASSOCIATES, AND LAND SURVE

MOMENEE


DATE: JULY 9, 2015


SHEET NO.

OF 4

SCALE: AS NOTED

FILE NO.: 15-155







SECTION VIEW


Manufactured by

(NON-TRAFFIC BEARING)

or other NPCA certified plant








NOTE: THE EXACT LOCATION AND DEPTH OF EXISTING UTILITIES CANNOT BE GUARANTEED. ALL UTILITIES DEPICTED ON THIS PLAN HAVE BEEN DEVELOPED FROM ABOVE GROUND OBSERVATIONS AND/OR EXISTING RECORDS. CONTRACTOR MUST VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. PENNSYLVANIA STATE LAW REQUIRES NOTIFICATION TO 1-800-242-1776 3-10 BUSINESS DAYS PRIOR TO ANY EXCAVATION.

DESIGN S/N: 20151422647




(SEE PLAN) 1 1/2" (MIN.) ID-2 WEARING COURSE 2 1/2" (MIN.) ID-2 BINDER COURSE

PREPARED SUBGRADE DRIVEWAY PAVING DETAIL Not To Scale



PROFILE VIEW PROVIDE MATERIALS AND CONSTRUCTION MEETING THE REQUIREMENTS OF PENNDOT PUBLICATION 72M, STANDARDS FOR ROADWAY CONSTRUCTION, RC-64M AND PADOT PUBLICATION 408, SECTION 630 FOR PLAIN CEMENT CONCRETE CURB.

DEPRESSED CURB FOR DRIVES Not To Scale



CLASS A CONCRETE CURB

1. MINIMUM 28-DAY COMPRESSIVE STRENGTH
OF 4000 PSI
2. CONTAIN 6% AIR-ENTRAINMENT BY VOLUME TYPICAL CURB DETAIL Not To Scale

PLAN LEGEND

INTERVAL)

	SUPPLEMENTAL CONTOUR (1'
	INDEX CONTOUR (5' INTERVA
	EXISTING STORM SEWER PIPI
s	EXISTING SANITARY SEWER P
	EXISTING GAS MAIN
	EXISTING WATER MAIN / SEF
T	EXISTING UNDERGROUND TEL
$\phantom{aaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaa$	EXISTING EDGE OF WOODS
	EXISTING EDGE OF PAVEMENT
——×—	EXISTING FENCE LINE
	PROPERTY LINE
	BUILDING SETBACK LINE
0	STORMWATER INFILTRATION TI
٨	CTODAWATED TECT DIT

RVICE LEPHONE STORMWATER TEST PIT BUILDING AREA

DRIVEWAY

WALKWAY/PATIO AREA

INFILTRATION BED NOTES

1. SCARIFY BOTTOM AND SIDES OF BASIN, TAKING CARE NOT TO COMPACT SOIL. 2. PERFORATED PIPE MUST HAVE PERFORATIONS NO LESS THAN 5/16" DIAMETER AND PROVIDE AN OPEN AREA OF NOT LESS THAN 3.31 SQUARE INCHES PER SQUARE FOOT OF 3. ENTIRE BED, SIDES TOP AND BOTTOM, SHALL BE WRAPPED IN PROPEX GEOTEX NON-WOVEN #1201 OR ENGINEER APPROVED EQUAL. PROVIDE A MINIMUM 1'OVERLAP AT ALL SEAMS AND JOINTS. WHERE PROTRUSIONS OR PENETRATIONS OCCUR, GEOTEXTILE SHALL BE PERMANENTLY AFFIXED TO OBJECT. 4. CARE SHOULD BE TAKEN IN THE PLACING OF STONE ATOP THE GEOTEXTILE SO AS TO AVOID TEARING OR RIPPING OF THE FABRIC. STONE SHOULD NOT BE DUMPED UNTIL A 6" LAYER OF STONE IS IN PLACE.


STORM WATER MANAGEMENT FACILITY OWNERSHIP AND MAINTENANCE NOTES:

ALL STORMWATER CONVEYANCE AND MANAGEMENT FACILITIES SHOWN ON THIS PLAN ARE PERMANENT AND ARE NOT TO BE REMOVED OR FILLED. THE INDIVIDUAL LOT OWNER, HIS/HER HEIRS, ASSIGNS OR SUCCESSORS SHALL BE RESPONSIBLE FOR THE PERPETUAL MAINTENANCE OF THE SAID FACILITIES. THE TOWNSHIP MAINTAINS THE RIGHT, BUT NOT THE RESPONSIBILITY, TO ENTER SAID PREMISES TO OBSERVE OR INSPECT THE FUNCTIONING OF THESE FACILITIES. IF THE PROPERTY OWNER, HIS/HER HEIRS, ASSIGNS, OR SUCCESSORS FAILS IN ANY WAY TO MAINTAIN THE SAID FACILITIES OR CAUSES THESE FACILITIES TO BE ALTERED OR REMOVED, UPON WRITTEN NOTIFICATION BY THE TOWNSHIP, THE DEFECTS SHALL PROMPTLY BE CORRECTED BY THE PROPERTY OWNER. UPON THE OWNER'S FAILURE TO CORRECT THE DEFECTS WITHIN TIME SPECIFIED BY THE TOWNSHIP, THE OWNSHIP, THE HEIRS, ASSIGNS, OR SUCCESSORS DO HEREBY AUTHORIZE THE TOWNSHIP AND/OR THEIR CONTRACTOR TO ENTER UPON THE SAID PROPERTY AND CAUSE THE REPAIR, MAINTENANCE, AND/OR CORRECTIONS TO BE MADE. A LIEN MAY BE FILED AGAINST THE PROPERTY FOR THE COSTS OF ALL CORRECTIONS INCLUDING APPLICABLE ENGINEERING AND/OR ATTORNEY'S FEES. THE TOWNSHIP IS UNDER NO OBLIGATION TO TAKE ANY ACTION. MAINTENANCE RESPONSIBLITIES SHALL INCLUDE THE FOLLOWING:

- MAINTAINING THE GRASS ON AND AROUND STORM WATER FACILITIES TO PREVENT LARGE VEGETATION AND ROOT SYSTEMS FROM GROWING ON OR NEAR FACILITIES AND TO PREVENT THE FORMATION OF NONVEGETATED AREAS THAT COULD FLOW INTO AND CLOG THE FACILITIES. THIS INCLUDES REGULAR WEEKLY MOWING.

 NO TREES OR SHRUBBERY MAY BE PLACED OVER THE LOCATION OF THE INFILTRATION BED.

 KEEPING ALL DEBRIS, INCLUDING GRASS CLIPPINGS, LEAVES, AND MOTOR OIL CLEAR OF INLET AND OUTLET STRUCTURES. THIS INCLUDES ROOF GUTTERS, INLET GRATES, AND OUTLET PIPES.
- REMOVING ANY ACCUMULATED DEBRIS IN INLETS.
 IF STORM WATER FACILITIES DO NOT DRAIN WITHIN 48 HOURS AFTER THE LAST STORM
 EVENT, THEY SHALL BE INSPECTED AND THEN FIXED OR REPLACED AS DETERMINED INLET AND OUTLET STRUCTURES SHALL BE INSPECTED MONTHLY. THE STONE BED SHALL BE INSPECTED ANNUALLY AND AFTER EVERY STORM EXCEEDING 1" OF RAINFALL.




PROVIDED VOLUME IN INFILTRATION BED #1: (72'Lx10'Wx5'D - PIPE VOLUME) X 40% VOIDS + 70 LF 36" DIA. PIPE VOLUME PROVIDED VOLUME = 945 + 495 = 1440 CF

└-6" CLEAN, WASHED AASHTO #3 ON TOP/BOTTOM OF PIPES

PROVIDED VOLUME IN INFILTRATION BED #2: (30'Lx10'Wx5'D - PIPE VOLUME) X 40% VOIDS + 28 LF 36" DIA. PIPE VOLUME PROVIDED VOLUME = 718 CF

2% MIN PIPE FROM BED-PERFORATED PIR BED 1 INV=276.5 BED 2 INV=275.5 PROFILE VIEW Perforated pipe must have perforations no less than 5/16" diameter and provide an open area of not less than 3.31 square PLAN VIEW inches per square foot of pipe surface.

LEVEL SPREADER DETAIL



EROSION AND SEDIMENTATION CONTROL NOTES . EROSION AND SEDIMENT BMPS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS.

2. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPS MUST BE STABILIZED IMMEDIATELY.

3. CONTRACTOR MUST WASH VEHICLE TIRES PRIOR TO LEAVING SITE. SHOULD WASHING TIRES PROVE INEFFECTIVE, CONTRACTOR MUST INSTALL ROCK CONSTRUCTION ENTRANCE.

4. CONTRACTOR MUST CLEAN DRIVEWAY AND ROAD OF ANY SEDIMENT AT THE END OF EACH WORK DAY. 5. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE

2:1 OR FLATTER. 6. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING

AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR

MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED.

ROBERT M. LAMBERT, P.E., ON THIS DATE, HEREBY CERTIFY THAT THE DRAINAGE P: 610-240-0450 PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE RADNOR TOWNSHIP STORMWATER MANAGEMENT ORDINANCE. PROFESSIONAL

RADNOR TOWNSHIP ROBERTAM LAMBER ENGINEER PE060743

ROBERT M. LAMBERT, P.E.

PE060743

DATE: 13 JULY 2015

PENNSYLVANIA

BUILDING PERMIT PLAN

F: 610-240-0451

PLAN PREPARED BY:

SITE ENGINEERING CONCEPTS, LLC

P.O. BOX 1992

SOUTHEASTERN. PA 19399

PLAN PREPARED FOR:

ROCKWELL DEVELOPMENT GROUP

446 BOXWOOD ROAD

ROSEMONT, PA 19101

DELAWARE COUNTY

GENERAL NOTES

4. THIS SURVEY IS NOT TO BE USED FOR TREE REMOVAL ALONG PROPERTY LINES. TREE

FIELD MARKED WITH STAKES SET TO ESTABLISH EXACT TREE OWNERSHIP.

5. THERE IS NO IDENTIFIABLE FLOOD PLAIN AREAS WITHIN THE PROJECT SITE AS

LOCATIONS ARE APPROXIMATE. FOR TREE REMOVAL PURPOSES, PROPERTY LINES MUST BE

ILLUSTRATED ON COMMUNITY PANEL NUMBER 420428-0038F OF THE FLOOD INSURANCE

RATE MAP AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY FOR THE

6. EXISTING SUBSURFACE UTILITY INFORMATION INDICATED IS BASED UPON VISUAL FIELD

INSPECTION BY JEFFERY P. TURNER, PLS. SUCH INFORMATION CONCERNING THE SIZE LOCATION, DEPTH, QUANTITY, ETC. OF SUBSURFACE UTILITIES IS APPROXIMATE IN NATURE

AND HAS BEEN OBTAINED AS A SUPPLEMENT TO THE SITE SURVEY. THE INFORMATION PROVIDED IS REPRESENTATIVE OF SUBSURFACE CONDITIONS ONLY AT LOCATIONS AND DEPTHS WHERE SUCH INFORMATION WAS OBTAINED. THERE IS NO EXPRESSED OR

IMPLIED AGREEMENT THAT UTILITY SIZE, LOCATION, DEPTH, QUANTITY, ETC. AS SHOWN

EXISTS BETWEEN EXPLORED LOCATIONS. ACCORDINGLY, UTILITY INFORMATION SHOWN SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. IT IS INCUMBENT UPON

THE CONTRACTOR TO VERIFY THE SIZE, LOCATION, DEPTH, QUANTITY, ETC. OF ALL

RECORD PLAN MINOR/FINAL SUBDIVISION/LOT LINE CHANGE 450,454,458 BOXWOOD

SOILS TAKEN FROM THE FOLLOWING WEBSITE: HTTP://WEBSOILSURVEY.SC.EGOV.USDA.GOV.

ROAD, MADE BY MOMENEE AND ASSOCIATES, INC., CIVIL ENGINEERS AND LAND SURVEYORS, BRYN MAWR, PA., DATED AUGUST 25, 2004 AND REVISED NOVEMBER

THE SITE'S SOIL ATTRIBUTE DATA IS SERVICED FROM THE NRCS SOIL DATA MART.

GeB2 - GLENELG CHANNERY SILT LOAM, 3 TO 8 PERCENT SLOPES, MODERATELY

GeD2 - GLENELG CHANNERY SILT LOAM, 15 TO 25 PERCENT SLOPES, MODERATELY

THE APPLICANT PROPOSES TO REMOVE THE EXISTING DWELLING, WALKWAY, PATIO

TWO INFILTRATION BEDS ARE PROPOSED TO PROVIDE GROUNDWATER RECHARGE AND WATER QUALITY TREATMENT AND CONTROL RATES PER THE TOWNSHIP

DURING CONSTRUCTION EROSION AND SEDIMENT CONTROL IS ACCOMPLISHED

THE LIMIT OF DISTURBANCE IS 25,000 SF (0.57 ACRES).

IMPERVIOUS COVERAGE SUMMARY

BUILDINGS

WALKS, WALLS & PATIO

TIMBERS & GRAVEL

TOTAL SITE IMPERVIOUS

BUILDING COVERAGE

TOTAL (SQ FT)

COVERAGE

THROUGH LIMITED DISTURBANCE, IMMEDIATE STABILIZATION, AND SILT FENCING.

REQUIREMENT

43,560 SF

120 FT

60 FT

35 FT

35 FT

REMOVE

25 FT / 60 FT

EXISTING

65,288 SF

120 FT

76 FT

45 FT / 118 FT

184 FT

35 FT

3.06%

35 FT

ADD

4174

PROPOSED

120 FT

107 FT

35 FT

26 FT / 93 F

PROPOSEI

AND DRIVEWAY AND CONSTRUCT A NEW DWELLING, WALKWAY, PATIO AND

ERODED, WELL DRAINED, HYDROLOGIC GROUP B.

ERODED, WELL DRAINED, HYDROLOGIC GROUP B.

3, 2004, AND RECORDED AS PLAN VOLUME 27 PAGE 139.

1. PARCEL INFORMATION:

DEED BOOK 2539 PAGE 1074

TOWNSHIP OF RADNOR, PENNSYLVANIA.

UTILITIES BEFORE EXCAVATION.

PROJECT NARRATIVE

ZONING SUMMARY

R-1 - RESIDENTIAL DISTRICT

MIN. LOT WIDTH @ BLDG

MAX. BUILDING HEIGHT

RIPARIAN BUFFER

MAX. BUILDING COVERAGE

SIDE (INDIVIDUAL/AGGREGATE)

ORDINANCE ITEM

MIN. LOT AREA

MIN. SETBACKS

FRONT

REAR

NUM. DATE

7. PLANS REFERENCED:

2. GROSS LOT AREA: 65,288 Sq. Ft.

Foilo# 36-07-04231-00 Block 36-30 Unit 172

LOT AREA CLEAR OF ROAD RIGHT OF WAY: 60,851 Sq. Ft.

3. ELEVATION BENCHMARK IS BASED ON THE BELOW REFERENCED PLAN.

SHEET 1 of 2

SCALE: 1" =30'

E:INFO@SITE-ENGINEERS.COM

(A)—— -10' OR TOTAL WIDTH OF ACCESS $(A) \longrightarrow$ PLAN VIEW SECTION A-A MAINTENANCE: Rock Construction Entrance thickness shall be constantly maintained to the specified dimensions by adding rock. A stockpile shall be maintanined on site ofr this prupose. At the end of each constrcution day, all sediment deposited on paved roadways shall be removed and returned to the construction site. ROCK CONSTRUCTION DETAIL

CONSTRUCTION STAGING

DRIVEWA)

AASHTO #1 ROCK~

GRADING AND EARTHMOVING OPERATIONS SHALL BE MINIMIZED DURING THE PERIOD FROM NOVEMBER 15 TO APRIL 1 WHEN RE-VEGETATION OF EXPOSED GROUND SURFACE IS DIFFICULT. MULICH STRAW STONE AND/OR SOD SHALL BE USED TO STABILIZE ALL AREAS DENUDED DURING THIS TIME PERIOD. CONTRACTOR MUST NOTIFY TOWNSHIP ENGINEER 48 HOURS PRIOR TO EARTH DISTURBANCE. NOTIFICATION IS SO AN INSPECTION CAN BE ARRANGED. TOWNSHIP ENGINEER SHALL ALSO BE NOTIFIED FOR INSPECTION PRIOR TO

INSTALLATION OF THE INFILTRATION BED AND PIPING. STAGE 1. INSTALL SILT FENCE, TREE PROTECTION FENCING AND ROCK CONSTRUCTION ENTRANCE.

STAGE 2. FIELD LOCATE ALL UTILITIES AND COORDINATE WITH UTILITIES FOR SHUTOFF/REMOVAL/RELOCATION AS NECESSARY. CAP AND MARK LOCATIONS AT SURFACÉ. IMMEDIATELY STABILIZE ANY DISTURBED AREAS. STAGE 3. REMOVE IMPROVEMENTS AS SHOWN. KEEP PORTIONS OF EXISTING PAVING AS LONG AS IS PRACTICAL TO USE AS STAGING AREAS. IMMEDIATELY STABILIZE AREAS WITH MULCH AND SEED MIX OR STONE, AS APPROPRIATE,

UNLESS IMMEDIATE CONSTRUCTION TAKES PLACE ON THESE AREAS.

STAGE 4. STRIP TOPSOIL AND ROUGH GRADE AREA OF PROPOSED IMPROVEMENTS. IMMEDIATELY STABILIZE DORMANT DISTURBED AREAS WITH THE APPROPRIATE SEED MIXTURE. TOPSOIL STOCKPILES ARE TO BE LIMITED TO 35 FEET WITH A MAXIMUM SIDE SLOPE OF 2:1. IMMEDIATELY STABILIZE STOCKPILE. STAGE 5. CONSTRUCT IMPROVEMENTS, DISTURBANCE SHALL BE KEPT TO A MINIMUM AT ALL TIMES, MAINTAIN ALL EROSION CONTROL FACILITIES AND DEVICES IN PROPER WORKING ORDER AT ALL TIMES. IMMEDIATELY STABILIZE

STAGE 6. COMPLETE CONSTRUCTION. PROPOSED PAVED AREAS SHALL BE IMMEDIATELY STABILIZED WITH STONE AFTER THEY ARE GRADED. IMMEDIATELY STABILIZE DORMANT DISTURBED AREAS WITH THE APPROPRIATE SEED MIXTURE. STAGE 7. CONSTRUCT STORMWATER INFILTRATION BEDS. CONTRACTOR MUST TAKE GREAT CARE TO ENSURE THAT NO SEDIMENT ENTERS THE BED. CLEAN WASHED STONE SHALL BE USED TO CONSTRUCT BEDS. IF SEDIMENT ENTERS STONE, STONE SHALL BE REPLACED AND THE GEOTEXTILE FABRIC SHALL BE CLEANED OR REPLACED AS NECESSARY. NO CONSTRUCTION TRAFFIC IS ALLOWED OVER BED EXCEPT FOR MINIMUM NECESSARY TO CONSTRUCT BED. NO FLOW SHALL ENTER BEDS FROM ANY AREAS THAT ARE NOT AT LEAST 70% STABILIZED WITH A UNIFORM VEGETATIVE COVER/STONE/IMPERVIOUS OR FULLY PROTECTED WITH INLET PROTECTION. IMMEDIATELY STABILIZE ALL DORMANT


DORMANT DISTURBED AREAS WITH STONE OR WITH TEMPORARY OR PERMANENT

SEED MIX AS WARRANTED AND MULCH AT 3 TONS PER ACRES, AND LIME AS

STAGE 8. ONCE SITE IS STABILIZED WITH 70% COVERAGE, CONTRACTOR MUST REMOVE EROSION AND SEDIMENTATION CONTROLS. AREAS DISTURBED DURING REMOVAL MUST BE STABILIZED IMMEDIATELY.


DISTURBED AREAS WITH THE APPROPRIATE SEED MIXTURE OR STONE

ANTICIPATED START OF CONSTRUCTION - FALL 2015 ANTICIPATED COMPLETION OF CONSTRUCTION - SUMMER 2016




AT DOWNSPOUTS DRAINING

TO INFILTRATION BED



DEMOLITION PLAN

SCALE: 1"=30"




FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL FABRIC WIDTH SHALL BE 42 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. AN 18 IN. SUPPORT STAKE SHALL BE DRIVEN 12 IN. MINIMUM INTO UNDISTURBED GROUND.

ELEVATION VIEW

SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.


STANDARD CONSTRUCTION DETAIL #4-8 **GRAPHIC SCALE** REINFORCED SILT FENCE (30" HIGH) 30



NOTE: THE EXACT LOCATION AND DEPTH OF EXISTING UTILITIES CANNOT BE GUARANTEED. ALL UTILITIES DEPICTED ON THIS PLAN HAVE BEEN DEVELOPED FROM ABOVE GROUND OBSERVATIONS AND/OR EXISTING RECORDS. CONTRACTOR MUST VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. PENNSYLVANIA STATE LAW REQUIRES NOTIFICATION TO 1-800-242-1776 3-10 BUSINESS DAYS PRIOR TO ANY EXCAVATION.


DESIGN S/N: 20151422647







LANDSCAPE SCHEDULE				
QTY	COMMON NAME	LATIN NAME	SIZE	NOTES
LARGE (CANOPY TREES:			
3	PIN OAK	QUERCUS PALUSTRIS	2.5-3 in Cal	B&B
4	RED MAPLE	ACER RUBRUM	2.5-3 in Cal	B&B
3	SARGENT CHERRY	PRUNUS SARGENTA	2.5-3 in Cal	B&B
4	SUGAR MAPLE	ACER SACCHARUM	2.5-3 in Cal	B&B
4	JAPANESE SERRATA	ZALKOVA SERRATA	2.5-3 in Cal	B&B
SMALL C	CANOPY TREES:			
3	EASTERN REDBUD	CERCIS CANADENSIS	6-8 FT	B&B
4	KOUSA DOGWOOD	CORNUS KOUSA	6-8 FT	B&B
4	CORNELIAN CHERRY	CORNUS MAS	6-8 FT	B&B
5	JAPANESE MAPLE	ACER PALMATUM	6-8 FT	B&B

TREE REPLACEMENT FORMULA				
	REPLACEMENT	TO BE REMOVED	REQUIRED	PROVIDED
6 TO 18 INCH DBH REMOVED	1 TREE	7	7 TREES	7 TREES
19 TO 29 INCH DBH REMOVED	3 TREES 2 BEING LARGE CANOPY	5	15 TREES 10 BEING LARGE CANOPY	15 TREES 10 BEING LARGE CANOPY
30 INCH DBH OR GREATER REMOVED	6 TREES 4 BEING LARGE CANOPY	2	12 TREES 8 BEING LARGE CANOPY	12 TREES 8 BEING LARGE CANOPY
TOTAL		14	34 TREES 18 BEING LARGE CANOPY	36 TREES 20 BEING LARGE CANOPY
			•	








EXISTING DECIDUOUS TREE



EXSITING EVERGREEN TREE



PROPOSED LARGE CANOPY TREE



PROPOSED SMALL CANOPY TREE

PLAN LEGEND


— — — INDEX CONTOUR (5' INTERVAL) ---- . EXISTING STORM SEWER PIPING ----s--- EXISTING SANITARY SEWER PIPING -----G ------ EXISTING GAS MAIN -----w------ EXISTING WATER MAIN / SERVICE T EXISTING UNDERGROUND TELEPHONE EXISTING EDGE OF WOODS ----- EXISTING EDGE OF PAVEMENT ------ PROPERTY LINE — — — — BUILDING SETBACK LINE

DRIVEWAY

----- SUPPLEMENTAL CONTOUR (1' INTERVAL) STORMWATER INFILTRATION TEST STORMWATER TEST PIT BUILDING AREA WALKWAY/PATIO AREA

10' Maximum Spacing Set a Minimum of 24" Into the Ground Fencing Must Be Attached to Post with 6 Gauge aluminum Wire Ties at 24" on Center Plastic Cable Ties May Not Be Used Reinstall All Damaged Fencing No Parking or Storage of Vehicles and or Materials Allowed Inside of Fenced Areas. Protection Barriers Shall be Maintained Throughout the Duration of the Work at Additional Warning Signs Should Also Be Placed on the Fencing and In Appropriate Areas Near The Work Zone PROTECTIVE TREE PRESERVATION FENCE DETAIL

RADNOR TOWNSHIP ROBERT M. LAMBERT, P.E. PE060743



SOUTHEASTERN, PA 19399

P: 610-240-0450 F: 610-240-0451

E:INFO@SITE-ENGINEERS.COM PLAN PREPARED FOR:

ROCKWELL DEVELOPMENT GROUP 446 BOXWOOD ROAD

ROSEMONT, PA 19101 DELAWARE COUNTY


LANDSCAPE PLAN

SHEET 2 of 2

SCALE: 1" =30'

PENNSYLVANIA

DATE: 13 JULY 2015







NOTIFY THE TOWNSHIP THAT CONSTRUCTION IS GOING TO COMMENCE. ANTICIPATED DATE: MAY 2014. REFER TO JULIP RUN STREAM RESTORATION PLANS FOR EROSION & SEDIMENT CONTROLS AND COMPLETE DETAILS. 2. INSTALL TREE PROTECTION AS INDICATED ON PLAN. FENCING MUST BE IN PLACE AND APPROVED PRIOR TO ANY DISTURBANCE. ALL DISTURBANCE SHALL BE CONTAINED TO THE DELINEATED LIMIT OF CONSTRUCTION. ALL CONSTRUCTION VEHICLES LEAVING THE SITE SHALL BE WASHED DOWN PRIOR TO ACCESS THE PUBLIC ROAD. SHOULD THIS PROVE INSUFFICIENT AT KEEPING DEBRIS OFF OF PUBLIC ROADWAYS, INSTALL A STABILIZED CONSTRUCTION ENTRANCE TO BE UTILIZED BY ALL CONSTRUCTION VEHICLES ENTERING/LEAVING 4. INSTALL DEWATERING FILTER BERM DOWNGRADE OF MATERIAL LEVELING AREA. ONCE THE DREDGING IN COMPLETE AND THE LEVELING AREA SHALL BE TEMPORARILY STABILIZED.

5. GRADE DREDGE CONTAINMENT AREA TO FACILITATE DEWATERING OF DREDGE 6. DRAW DOWN POND USING APPROVED METHODS AND HAND TRANSFER FISH TO ONE OF THE UPPER PONDS (POND 3 OR 4).

7. REMOVE MATERIAL FROM POND AND PLACE WITHIN THE CONTAINMENT AREA FOR DEWATERING. TO THE EXTENT POSSIBLE THE MATERIAL SHALL BE PLACED IN A MANNER TO CREATE A SMOOTH TRANSITION FROM TOE OF SLOPE TO THE REMAINING EXISTING GRADE. 8. INSPECT SEDIMENT BARRIERS FREQUENTLY, ESPECIALLY AFTER HEAVY STORMS.

9. UNTIL THE SITE IS STABILIZED ALL EROSION AND SEDIMENTATION CONTROLS MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROLS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK; INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING. AND RENETTING. MUST BE PERFORMED IMMEDIATELY. 10. AFTER COMPLETION OF PLACEMENT OF THE DREDGE MATERIAL, IMMEDIATELY SEED AND MULCH THE CONTAINMENT AREA. ALL AREAS DISTURBED CONSTRUCTION SHALL BE GROOMED AND RESEEDED AS NECESSARY TO RESTORE THEM BACK TO THEIR ORIGINAL CONDITION.

11. CONSTRUCTION FINISHED. ANTICIPATED: JUNE 2014.

REPLACE AND REPAIR SEDIMENT BARRIERS AS NECESSARY.

EROSION AND SEDIMENT CONTROL NOTES: 1. UNTIL THE SITE ACHIEVES FINAL STABILIZATION, THE PERMITTEE AND COPERMITTEE SHALL ASSURE THAT THE BEST MANAGEMENT PRACTICES ARE IMPLEMENTED, OPERATED, AND MAINTAINED PROPERLY AND COMPLETELY. ALL MAINTENANCE WORK, INCLUDING CLEANING, REPAIR, REPLACEMENT, REGARDING, RESEEDING, AND RESTABILIZATION SHALL BE PERFORMED IMMEDIATELY.

2. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION. 3. THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE MUNICIPALITY, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL AND/OR ROCK SPOIL AND BORROW AREAS, REGARDLESS OF

THEIR LOCATIONS. 4. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS. 5. EROSION AND SEDIMENT BMP'S MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMP'S. 6. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMP'S MUST BE STABILIZED IMMEDIATELY.


7. AT LEAST 3 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INCORPORATED AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS. 8. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS. 9. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT

HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER

10. SEDIMENT MUST BE REMOVED FROM STORM WATER INLET PROTECTION AFTER EACH RUNOFF EVENT.

11. HAY OR STRAW MULCH MUST BE APPLIED AT 3.0 TONS PER ACRE. 12. SOD, MULCH WITH MULCH CONTROL NETTING, OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 4:1 OR STEEPER. 13. STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY

14. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGARDING, RESEEDING, REMULCHING, AND RENETTING, MUST BE DONE IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S, OR MODIFICATIONS TO THOSE INSTALLED WILL BE REQUIRED. 15. THE OPERATOR SHALL REMOVE FROM THIS SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THIS SITE. 16. PROVIDE CONSTRUCTION FENCING AS NECESSARY TO SECURE THE CONSTRUCTION SITE FROM UNAUTHORIZED ACCESS.



LOCATION MAP SCALE: 1" = 1,000'


NOTE: DREDGING OF PONDS 1 & 2 LIMITED TO APPROXIMATELY 2,500-CY

EROSION CONTROL LEGEND

XXXXXXXXXXXX TREE PROTECTION FENCING

CONSTRUCTION ENTRANCE

LINETYPE LEGEND — — — — — EXISTING PROPERTY LINE EXISTING FLOODPLAIN ——— — — EXISTING EDGE OF STREAM - · - EXISTING TOWNSHIP LINE ---- EXISTING WATERCOURSE _____ EXISTING 2' CONTOUR



PONDS 1 & 2 DREDGING MOMENEE & ASSOCIATES, INC. CIVIL ENGINEERS AND LAND SURVEYORS

924 COUNTY LINE ROAD, BRYN MAWR, PA 19010 PHONE: (610) 527-3030 FAX: (610) 527-9008

SHEET NO.

OF 1

SCALE: 1" = 40'


FILE NO.: 11-218

DATE: FEBRUARY 20, 2014 EROSION & SEDIMENT CONTROL PLAN RAVENSCLIFF - ROUNDHILL

RADNOR TOWNSHIP * DELAWARE COUNTY * PENNSYLVANIA ONE—CALL: | 20131342261 RAVENSCLIFF - ROUNDHILL DRAWN BY: HOMEOWNERS ASSOCIATION CHECKED BY: MJB

Serial Number: 20131342261 CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE—STOP CALL ∜ Pennsylvania One Call System, Inc. 1-800-242-1776

THE THIRD PARTY'S SOLE RISK AND WITHOUT LIABIU (POSURE TO MOMENEE AND ASSOCIATES, INC. THE TH L FURTHER INDEMNIFY AND HOLD HARMLESS MOMENEE





PREVIOUSLY APPLIED FOR UNDER A SEPARATE GRADING PERMIT

ENGINEER PE061543

LINETYPE LEGEND

- · - · EXISTING TOWNSHIP LINE ---- EXISTING WATERCOURSE ---- EXISTING 2' CONTOUR — — — — — EXISTING 10' CONTOUR

- ---- EXISTING EDGE OF STREAM

----- EXISTING FLOODPLAIN

PONDS 1 & 2 DREDGING

MOMENEE & ASSOCIATES, INC. CIVIL ENGINEERS AND LAND SURVEYORS 924 COUNTY LINE ROAD, BRYN MAWR, PA 19010 PHONE: (610) 527-3030 FAX: (610) 527-9008

EROSION & SEDIMENT CONTROL PLAN
RAVENSCLIFF - ROUNDHILL
RADNOR TOWNSHIP * DELAWARE COUNTY * PENNSYLVANI

OWNER/APPLICANT RAVENSCLIFF — ROUNDHILL HOMEOWNERS ASSOCIATION ONE-CALL: 20131342261 DRAWN BY: JRM CHECKED BY: MJB

SHEET NO. OF 3 SCALE: 1" = 40' FILE NO.: 11-218

DATE: FEBRUARY 20, 2014

CONSTRUCTION ENTRANCE

LOCATION MAP SCALE: 1" = 1,000'

PENNSYLVANIA LAW REQUIRES
3 WORKING DAYS NOTICE FOR
CONSTRUCTION PHASE AND 10 WORKING
DAYS IN DESIGN STAGE—STOP CALL Pennsylvania One Call System, Inc. 1-800-242-1776

Serial Number: 20131342261

1 INCH = 40 FT.

<u>HYDROSEEDING SPECIFICATIONS</u> DEFINITION: STABILIZING SEDIMENT PRODUCING AND SEVERELY

ERODED AREAS BY ESTABLISHING PERMANENT GRASS

APPLICATION RATE

(PER ACRE)

PURPOSE: TO PROVIDE PERMANENT VEGETATIVE COVER TO CONTROL RAPID RUN-OFF AND EROSION.

PROCEDURE: SURFACE TO BE HYDRO-SEEDED SHALL BE CLEANED OF ALL DEBRIS AND OTHER MATTER HARMFUL TO UNIFORM GERMINATES. A WATER-SLURRY MIXTURE COMPOSED OF THE BELOW MENTIONED "MATERIALS" SHALL BE SPRAYED UNIFORMLY OVER THE AREAS TO BE HYDRO-SEEDED.

MATERIALS:

<u>PERMANENT SEEDING</u> APPLICATION RATE DESCRIPTION (PER ACRE)

** SEE SPECIFICATIONS *

MPORARY	
ME	DESCRIPTION

1) SEED	ANNUAL RYEGRASS (95% PURE)	40 LBS.
2) COMMERCIAL FERTILIZER	5–5–5	1,000 LB
3) LIME	GROUND AGRICULTURAL LIMESTONE (MAY BE APPLIED SEPARATELY)	1 TON
4)	HAY OR STRAW	3 TONS

PLACING TOPSOIL OR TOPSOIL MIXTURE

PREPARATION OF AREAS TO BE TOPSOILED

GRADE THE AREAS TO BE COVERED BY TOPSOIL. USING ACCEPTABLE METHODS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE PLACING THE TOPSOIL. REMOVE STONES AND OTHER FOREIGN MATERIAL 2 INCHES OR LARGER IN DIMENSION. REMOVE AND SATISFACTORILY DISPOSE OF UNSUITABLE AND SURPLUS MATERIAL.

PLACING AND SPREADING TOPSOIL

PLACE TOPSOIL ON THE PREPARED AREAS AND, UNLESS OTHERWISE INDICATED. SPREAD AND COMPACT TO A 4-INCH UNIFORM DEPTH \pm 1 1/2 INCHES. COMPACT WITH A ROLLER WEIGHING NOT OVER 120 POUNDS PER FOOT WIDTH OF ROLLER OR BY OTHER ACCEPTABLE METHODS, AS DIRECTED. REMOVE OVERDEPTH TOPSOIL, UNLESS OTHERWISE AGREED UPON IN WRITING. DO NOT PLACE TOPSOIL IN A WET OR FROZEN CONDITION.

<u>SEEDING SPECIFICATIONS:</u>

WHERE DENUDED AREAS ARE DESIRED TO BE LAWN:


PERFORM ALL CULTURAL OPERATION AT RIGHT ANGLES TO THE


APPLY LIME ACCORDING TO TEST OR AT THE RATE OF 25 LBS. OF GROUND LIMESTONE PER 1,000 SQ. FT. APPLY FERTILIZER ACCORDING TO SOIL TEST OR WORK IN DEEPLY 20 LBS. OF 0-20-20 OR EQUIVALENT PER 1,000 SQ. FT.

AND AT THE TIME OF SEEDING, WORK INTO THE SURFACE 10 LBS. OF

10-10-10 OR EQUIVALENT PER 1,000 SQ. FT. OR OTHER APPROVED

- 4. SMOOTH AND FIRM SEEDED PRIOR TO SEEDING.
- 5. SEED USING SPECIFIED MIXTURE AND RATE.
- 6. STABILIZE WITH EROSION CONTROL BLANKETS AS NOTED ON





 \mid COMPOST SHALL MEET STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANU COMPOST FILTER BERMS SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BERM SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BERM

THE MAXIMUM SLOPE LENGTH ABOVE A COMPOST FILTER BERM SHALL NOT EXCEED THAT SHOWN IN TABLE 4.4 OF THE PA DEP EROSION CONTROL MANUAL FOR THE STANDARD SILT FENCE (18 IN. HIGH FENCE).

TALL GRASS SHALL BE CUT PRIOR TO INSTALLATION TO MINIMIZE POTENTIAL FOR \mid undercutting. Berm shall be netted or otherwise anchored after installation.

I ALIGNMENT

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE ABOVE GROUND HEIGH

ANY SECTION COMPOST FILTER BERM WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED. CONCENTRATED FLOWS SHALL NOT BE DIRECTED TOWARD ANY

> STANDARD CONSTRUCTION DETAIL #4-2 COMPOST FILTER BERM

MAINTENANCE OF TEMPORARY SEDIMENTATION CONTROL STRUCTURES

A ROUTINE "END OF DAY CHECK" SHALL BE MADE DURING CONSTRUCTION TO MAKE SURE THAT ALL CONTROL MEASURES ARE WORKING PROPERLY. ALL PERSONS ENGAGED IN LAND DISTURBANCE ACTIVITIES SHALL PREVENT ACCELERATED EROSION AND SEDIMENTATION. THERE SHALL BE NO ADVERSE DISCHARGE OF THE SEDIMENT OR OTHER SOLID MATERIALS FROM THE SITE AS A RESULT OF STORMWATER RUNOFF UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROL AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING MUST

STABILIZED CONSTRUCTION ENTRANCE: THE STABILIZED CONSTRUCTION ENTRANCES ARE TO BE CONSTRUCTED PER THE DETAIL. THICKNESS WILL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL WILL BE MAINTAINED ON THE SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PUBLIC ROADWAYS WILL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.

SILT SOXX: SILT SOXX SHALL BE INSTALLED PER THE DETAIL. SEDIMENT SHALL BE REMOVED FROM SILT FENCES WHEN IT REACHES 1/3 THE BERM HEIGHT OR AS DIRECTED BY THE MUNICIPAL ENGINEER. SILT SOXX WHICH HAS BEEN UNDERMINED OR TOPPED WILL BE REPLACED IN KIND OR WITH ROCK FILTER OUTLETS

SEDIMENT DISPOSAL: SILT REMOVED FROM TEMPORARY SEDIMENT CONTROL STRUCTURES SHALL BE DISPOSED OF ON—SITE IN LANDSCAPED AREAS LOCATED OUTSIDE OF FLOOD PLAINS, WETLANDS, STEEP SLOPES AND DRAINAGE SWALES.

DUST CONTROL: DUST AND OTHER PARTICLES SHALL BE KEPT WITHIN TOLERABLE LIMITS BY USING WATER. APPLICATION SHALL BE AS NEEDED OR AS DIRECTED BY THE MUNICIPAL ENGINEER OR THE CONSERVATION DISTRICT. USE OF CALCIUM CHLORIDE OR OTHER SIMILAR APPROVED AGENTS SHALL BE LIMITED TO ONLY THOSE PARTICULAR SITUATIONS IN WHICH PERIODIC CLEANING AND/OR WETTING IS NOT FEASIBLE DUE TO CONDITIONS CAUSED BY WEATHER, TRAFFIC, ETC.

MAINTENANCE/PERFORMANCE OF BARRIERS: * INSPECT BARRIERS FOR SEDIMENT ACCUMULATIONS AND REMOVE SEDIMENTS WHEN

BE PERFORMED IMMEDIATELY.

- THE DEPTH REACHES ONE-THIRD OF DAM/BARRIER HEIGHT. DISPOSE OF SEDIMENTS IN AN APPROVED AREA AND STABILIZE. * INSPECT BEFORE, DURING AND AFTER EACH RAINFALL EVENT, AND DAILY THROUGHOUT USE
- * RESHAPE OR REPLACE SAND BAGS AND REPOSITION CONCRETE BARRIERS AS NFFDFD. * REPAIR WASHOUTS OR OTHER DAMAGE AS NEEDED * REMOVE THE DAM/BARRIER ONLY AFTER ACCUMULATED SEDIMENTS HAVE BEEN

REMOVED AND DISPOSED OF IN AN APPROVED MANNER. THE SANDBAGS SHOULD BE REMOVED BY HAND TO PREVENT BREAKAGE AND FURTHER DISTURBANCE OF THE

EROSION AND SEDIMENT CONTROL NOTES:

RECEIVING WATER: SCHUYLKILL RIVER

CHAPTER 93 CLASSIFICATION: WWF, MF 01. ALL SLOPES 3:1 OR STEEPER WILL BE STABILIZED WITH AN EROSION CONTROL BLANKET AS NOTED ON THE PLANS UNLESS

02. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL SITE INSPECTIONS WILL BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE. THE COMPLIANCE ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE INSPECTION LOG WILL BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO THE DISTRICT UPON REQUEST.

ALL PREVENTIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGARDING, RESEEDING, REMULCHING AND RENETTING, MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENTATION BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S OR MODIFICATIONS OF THOSE INSTALLED WILL BE NEEDED.

WHERE BMP'S ARE FOUND TO FAIL TO ALLEVIATE EROSION ON SEDIMENT POLLUTION THE PERMITTEE OR CO-PERMITTEE SHALL

A. THE LOCATION AND SEVERITY OF THE BMP'S FAILURE AND ANY POLLUTION EVENTS.
B. ALL STEPS TAKEN TO, REDUCE, ELIMINATE AND PREVENT THE RECURRENCE OF THE NON-COMPLIANCE.
C. THE TIME FRAME TO CORRECT THE NON-COMPLIANCE, INCLUDING THE EXACT DATES WHEN THE ACTIVITY WILL RETURN TO

SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS.

AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP'S MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMP'S MUST BE STABILIZED IMMEDIATELY. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED

03. BEFORE INITIATING ANY REVISION TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION. THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR

04. ALL PUMPING OF SEDIMENT LADEN WATER OR POTENTIALLY SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NONDISTURBED AREAS. SEDIMENT REMOVED FROM BMP'S SHALL BE DISPOSED OF IN LANDSCAPE AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES

05. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64 ,EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION

06. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE COUNTY CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL AND/OR ROCK SPOIL AND BORROW AREAS, REGARDLESS OF THEIR LOCATION.

07. THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. AND 287.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES

08. NEWLY GRADED SLOPES TWENTY FIVE PERCENT (25%) OR GREATER SHALL BE IMMEDIATELY SODDED OR STABILIZED WITH THE APPROPRIATE EROSION CONTROL BLANKET OR MATTING.

09. UPON COMPLETION OR TEMPORARY CESSATION OF ANY EARTH DISTURBANCE ACTIVITY, OR ANY PHASE THEREOF, THE PROJECT SITE SHALL BE IMMEDIATELY STABILIZED WITH THE APPROPRIATE TEMPORARY OR PERMANENT STABILIZATION.

10. SHOULD UNFORESEEN EROSIVE CONDITIONS DEVELOP DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ACTION TO REMEDY SUCH CONDITIONS AND TO PREVENT DAMAGE TO ADJACENT PROPERTIES AS A RESULT OF INCREASED RUNOFF/AND OR SEDIMENT DISPLACEMENT. THE CONTRACTOR SHALL PLAN FOR AVAILABLE SOURCES OF WOODCHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES IN ORDER TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.

11. THE CONTRACTOR SHALL, BY SCHEDULING THE CONSTRUCTION, UTILIZE NEW PLANTINGS AND PROPERLY INSTALL EROSION CONTROL FENCING, HAY BALES AND OTHER EROSION CONTROL MEASURES TO MINIMIZE EROSION DAMAGE.

ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED MUST BE SEEDED AND MULCHED IMMEDIATELY. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE RECOMMENDED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN ONE YEAR MAY BE SEEDED AND MULCHED WITH A QUICK GROWING TEMPORARY SEEDING MIXTURE AND MULCH. DISTURBED AREAS WHICH ARE EITHER AT FINISHED GRADE OR WILL NOT BE REDISTURBED WITHIN ONE YEAR MUST BE SEEDED AND MULCHED IMMEDIATELY.


13. A ROUTINE "END-OF-DAY-CHECK" SHALL BE MADE DURING CONSTRUCTION TO MAKE SURE THAT ALL CONTROL MEASURES ARE WORKING PROPERLY. ALL PERSONS ENGAGED IN LAND DISTURBANCE ACTIVITIES SHALL DESIGN, IMPLEMENT, AND MAINTAIN CONTROL MEASURES WHICH PREVENT ACCELERATED EROSION AND SEDIMENTATION. THERE SHALL BE NO ADVERSE DISCHARGE OF THE SEDIMENT OR OTHER SOLID MATERIALS FROM THE SITE AS THE RESULT OF STORM WATER RUNOFF.

14. TEMPORARY EROSION CONTROL MEASURES MAY BE REMOVED ONLY AFTER THE CONSTRUCTION AREA AND CONTAINED SILT IS STABILIZED AND THE LAWN AREA ESTABLISHED. I.5. ALL PERSONS ENTERING ACTIVE TANKS, MANHOLES, INLETS, ETC. MUST COMPLY WITH OSHA REQUIREMENTS FOR ENTRY INTO

16. ON-SITE TREES TO BE SAVED SHALL BE PREPARED FOR CONSTRUCTION BY APPROPRIATE FERTILIZATION AND PROTECTED BY

17. THE PERMITTEE MUST DEVELOP, AND HAVE APPROVED BY THE DISTRICT, A SEPARATE EROSION AND SEDIMENTATION CONTROL PLAN FOR EACH SPOIL, BORROW, OR OTHER WORK AREA NOT DETAILED IN THE PERMITTED PLAN, WHETHER LOCATED WITHIN OR 18. GRADING EQUIPMENT SHALL NOT BE ALLOWED TO CROSS PERMANENT OR INTERMITTENT STREAMS PRIOR TO OBTAINING THE

19. NO EXCAVATIONS OR FILLS THAT ENCROACH ON NATURAL WATERCOURSES, FLOOD HAZARD AREAS, CONSTRUCTED CHANNELS, OR WETLANDS SHALL OCCUR WITHOUT THE NECESSARY STATE AND/OR FEDERAL PERMITS.





- 1. PROTECTION BARRIERS SHALL BE 6 FEET HIGH, CONSTRUCTED OF 2" CHAIN LINK MESH FABRIC.

2. FABRIC SHALL BE SECURED TO 2" POSTS WITH 6 GA. ALUMINUM WIRE TIES AT 24" O.C.

- 3. POSTS SHALL BE A MINIMUM OF 2 FEET IN THE GROUND AND SPACED 10 FEET ON CENTER MAX.
- 4. PLASTIC ZIP-TIES MAY NOT BE USED TO SECURE FABRIC TO POSTS.

TREE PROTECTION BARRIER FENCING





EROSION AND SEDIMENT CONTROL NOTES (CONTINUED):

FOLLOWING COMPLETION OF DISTURBANCE.

20. STORMWATER MANAGEMENT FACILITIES SHALL BE PROTECTED FROM SEDIMENT LADEN MATERIAL DURING CONSTRUCTION.

21. CARE SHOULD BE EXERCISED IN ALL DISTURBANCE ACTIVITIES TO PREVENT DEGRADATION TO THE WATERS OF THE COMMONWEALTH. UPON COMPLETION OR TEMPORARY CESSATION OF EARTH DISTURBANCE ACTIVITIES, THE PROJECT SITE MUST BE IMMEDIATELY STABILIZED WITH THE APPROPRIATE TEMPORARY OR PERMANENT STABILIZATION.

22. TO PROTECT ADJACENT PROPERTIES, ALL AREAS REQUIRING INTERIM STABILIZATION MUST BE ADDRESSED IMMEDIATELY

23. SHOULD ANY TREES NOT SCHEDULED OR PERMITTED TO BE REMOVED BE IRREPARABLE DAMAGED DURING CONSTRUCTION AND DIE WITHIN (18) MONTHS OF THE CONCLUSION OF CONSTRUCTION ACTIVITIES, THOSE TREES WILL BE REQUIRED TO BE REPLACED.

24. TEMPORARILY SEED ALL STOCKPILE TOPSOIL. IMMEDIATELY TEMPORARILY SEED ALL TEMPORARY E & S CONTROL AREAS.

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCE, OR IN 26. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON

PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW OR EQUIVALENT MATERIAL, AT A RATE OF 3.0 TONS PER ACRE. 27. PERMANENT VEGETATION TO BE SEEDED ON ALL EXPOSED AREAS IMMEDIATELY AFTER FINAL GRADING. MULCH TO BE USED

AS NECESSARY FOR PROTECTION UNTIL SEEDING IS ESTABLISHED. HAY OR STRAW MULCH MUST BE APPLIED AT 3.0 TONS PER ACRE. MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 3:1 OR STEEPER. STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN.

28. ALL WORK WILL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION, THE COUNTY, AND THE MUNICIPALITY. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED.

29. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING ALL CRITICAL AREAS SUBJECT TO EROSION (I.E. STEEP SLOPES AND EMBANKMENTS) WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR SUITABLE EQUIVALENT, AT A RATE OF 3.0 TONS PER ACRE. MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 3:1 OR STEEPER. STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR

30. A STABILIZED CONSTRUCTION ENTRANCE PAD OF 1.5" TO 2" SIZE CLEAN STONE WILL BE PLACED AT ALL CONSTRUCTION DRIVEWAYS IMMEDIATELY AFTER INITIAL SITE DISTURBANCE. DIMENSIONS: LENGTH — NOT LESS THAN 50 FT. EXCEPT ON SINGLE RESIDENCE LOT WHERE 30 FT. MINIMUM WOULD APPLY, WIDTH — 10 FT. MINIMUM, BUT NOT LESS THAN THE FULL WIDTH OF THE ENTRANCE OR EXIT DRIVES, DEPTH — NOT LESS THAN 6". FILTER CLOTH IS REQUIRED PRIOR TO STONE PLACEMENT EXCEPT

31. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN WILL REQUIRE THE SUBMISSION OF REVISED EROSION AND SEDIMENT CONTROL PLANS TO THE DISTRICT CONSERVATION OFFICE FOR REVIEW. BEFORE INITIATING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE COUNTY

32. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIA VEGETATIVE COVER OF OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS. MULCH MUST BE APPLIED AT THE SPECIFIC RATES. DISTURBED AREAS WHICH AREA NOT AT FINISHED GRADE AND WHICH WILL BE REDISTRURBED WITHIN 1-YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH AREA AT FINISHED GRADE OR WHICH will not be redisturbed within 1—year must be stabilized in accordance with the permanent vegetative stabilization

33. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE 2:1 OR FLATTER.

34. IN CONJUNCTION WITH EARTHMOVING ACTIVITY, INSTALL THE DESIGNED CONSERVATION MEASURES IN ACCORDANCE WITH SUBMITTED PLANS AND SPECIFICATIONS.

A) INSTALL SEDIMENT BARRIERS AS CLOSE TO CONTOURS AS POSSIBLE. BARRIERS WILL BE CHECKED PERIODICALLY DAMAGED BARRIERS ARE TO BE REPLACED AND SEDIMENT WHICH IS COLLECTED BY THE BARRIER WILL BE REMOVED AND SPREAD AND STABILIZED WITH VEGETATION ELSEWHERE ON THE SITE. B) SEDIMENT SHALL NOT BE ALLOWED TO ACCUMULATE HIGHER THAN ONE FOOT ABOVE EXISTING GRADE. SEE DETAILS FOR SEDIMENT BARRIER TYPE AND INSTALLATION PROCEDURES. C) DURING CONSTRUCTION, ALL SEDIMENT TRAPPED AT BARRIERS SHALL BE CLEANED OUT AFTER EACH EROSION PRODUCING

35. TOPSOIL TAKEN FROM CONSTRUCTION AREAS SHALL BE SEEDED WITH VEGETATIVE COVER AND STOCKPILED FOR RE-USE IN


36. GEOTEXTILE FABRIC SHALL BE CLASS 1. GEOTEXTILE FABRIC IN ACCORDANCE WITH PENNDOT SPECIFICATION FROM 408. THE TYPE AND/OR THICKNESS SHALL BE DUPONT TYPAR #3401, AMOCO PROPEX #4545 OR APPROVED EQUAL OR AS OTHERWISE

AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS.

A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE PERMITTEE SHALL CONTACT THE DEPARTMENT OR AUTHORIZED CONSERVATION DISTRICT AT LEAST SEVEN DAYS BEFORE CONSTRUCTION IS TO BEGIN TO DETERMINE IF A PRECONSTRUCTION CONFERENCE IS REQUIRED. THE PERMITTEE AND OTHERS INDERTAKING THE EARTH DISTURBANCE ACTIVITY MUST ATTEND A PRECONSTRUCTION CONFERENCE WHEN REQUESTED BY THE DEPARTMENT OR AUTHORIZED CONSERVATION DISTRICT. THE PERMITTEE MUST BRING A COPY OF THEIR PERMIT, A COPY OF THE STAMPED PLAN FROM THE CONSERVATION DISTRICT, AND ALL ASSOCIATED DEPARTMENT APPROVALS/PERMITS WHICH MUST BE AVAILABLE AT THE CONFERENCE UPON REQUEST. ALSO, AT LEAST 3 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INCORPORATED

UPON THE INSTALLATION OR STABILIZATION OF ALL PERIMETER SEDIMENT CONTROL BMPS AND AT LEAST 3 DAYS PRIOR TO PROCEEDING WITH THE BULK EARTH DISTURBANCE ACTIVITIES, THE PERMITTEE OR CO-PERMITTEE SHALL PROVIDE NOTIFICATION TO THE DEPARTMENT OR AUTHORIZED CONSERVATION DISTRICT.

PERMITTEES AND CO_PERMITTEES ARE RESPONSIBLE FOR ENSURING THAT A LICENSED PROFESSIONAL(S) HAVE OVERSIGHT RESPONSIBILITIES FOR THE DESIGN AND PROPER INSTALLATION OF ALL STREAM BANK RESTORATION IMPROVEMENTS. THE LICENSED PROFESSIONAL(S) SHALL CERTIFY THAT THESE IMPROVEMENTS HAVE BEEN INSTALLED IN ACCORDANCE WITH THE APPROVED PLAN. THE INSTALLATION SCHEDULE AND MAINTENANCE REQUIREMENTS CONTAINED WITHIN THE APPROVED PLAN MUST BE FOLLOWED; AND FAILURE TO COMPLY WITH THE INSTALLATION SCHEDULE IS A VIOLATION OF THIS PERMIT, THE CLEAN STREAMS LAW, AND THE CLEAN WATER ACT.



FILTER FABRIC FENCE MUST BE PLACED AT LEVEL GRADE. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8' UP SLOPE AT 45' TO THE MAIN BARRIER ALIGNMENT. ANY SILT FENCING WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE REPLACED WITH ROCK FILTER OUTLETS IMMEDIATELY. SEE ROCK FILTER OUTLET DETAIL.

SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT THE FENCE.

STANDARD FILTER FABRIC FENCE

PONDS 1 & 2 DREDGING

MOMENEE & ASSOCIATES, INC CIVIL ENGINEERS AND LAND SURVEYORS 924 COUNTY LINE ROAD, BRYN MAWR, PA 19010 PHONE: (610) 527-3030 FAX: (610) 527-9008

EROSION & SEDIMENT CONTROL PLAN RAVENSCLIFF - ROUNDHILL

RADNOR TOWNSHIP * DELAWARE COUNTY * PENNSYLVANIA ONE-CALL: | 20131342261 RAVENSCLIFF - ROUNDHILL DRAWN BY: HOMEOWNERS ASSOCIATION CHECKED BY: MJB

DATE: FEBRUARY 20, 2014 SHEET NO. OF SCALE: AS NOTED

FILE NO.: 11-218

THE AND ASSOCIATES, INC. CONSULTING ENGINEERS, EXPRESSLY ES ITS COMMON LAW COPYRIGHT AND ALL OTHER PROPRIETARY IN THESE PLANS. ALL DRAWINGS, SPECIFICATIONS AND THEREOF ARE AND SHALL REMAIN THE PROPERTY OF MOMENEE E AT THE THIRD PARTY'S SOLE RISK AND WITHOUT LIABILI' AL EXPOSURE TO MOMENEE AND ASSOCIATES, INC. THE THIS SHALL FURTHER INDEMNIFY AND HOLD HARMLESS MOMENEE AI






RADNOR TOWNSHIP SHADE TREE COMMISSION

Hazardous Tree Report Resident ME Tree (Type, species, size, diameter at breast height) Certified arborist's narrative report (attach separate sheet if required) Certified arborist's name, address and # Pictures attached Plot plan drawing attached _ Township arborist's report (attach separate sheet if required)_

Shade Tree Commission removal recommended yes / no

The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.











RADNOR TOWNSHIP SHADE TREE COMMISSION


Hazardous Tree Report

Resident Scott Evans
Address 304 Landover Road, Bryn Mawr
Tree (Type, species, size, diameter at breast height) 31" Red oak tree
Certified arborist's narrative report (attach separate sheet if required) There is obvious decay on central leader at approximately 30'. Tree seems to have slight crack or
opening along trunk, possibly due to June wind storm. I would recommend this tree for removal
due to the decay area along the main trunk and the crack along the trunk.
Certified arborist's name, address and # James B. Ward, PD-0053
Pictures attached X Plot plan drawing attached
Township arborist's report (attach separate sheet if required)

Shade Tree Commission removal recommended yes / no

The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.







Jones, Suzan

From:

Jones, Suzan <sjones@radnor.org>

Sent:

Wednesday, July 08, 2015 3:18 PM

To:

'GINA MAMMUCARI'

Cc:

'john@rickstreeservice.com'

Subject:

RE: 320 LOUELLA AVE

The Township Arborist has given permission to remove, under the condition that the homeowner plant one (1) shade tree to compensate for the canopy loss. Please provide species once the decision is made.

Thank you if you need any further information, please do not hesitate to contact me.

Suzan Jones

Administrative Assistant Radnor Township Engineering Department 301 Iven Ave. Wayne, Pa 19087

P) 610.688. 5600 Ext 133 F) 610.971.0450 sjones@radnor.org

To focus on something you want to achieve no matter how small;
Is more relevant than focusing on something you've already accomplished.

-----Original Message-----

From: GINA MAMMUCARI [mailto:GINA@RICKSTREESERVICE.COM]

Sent: Wednesday, July 08, 2015 1:50 PM

To: 'Jones, Suzan'

Cc: john@rickstreeservice.com Subject: 320 LOUELLA AVE

Hi Sue,

We are requesting a permit to remove a tree at 320 Louella Ave. Please see attached application and photos.

Thank you,

Gina Mammucari Rick's Tree Service 610-358-1953






RADNOR TOWNSHIP SHADE TREE COMMISSION HEIGHOUS THE REPORT

Resident spot Marke (Beer Suchorm) Address Tree (Type, species, size, diameter at breast height) Certified arborist's narrative report. (attach separate sheet if required) Trac indominant Sleme and sound out out Certified arborist's name, address and # Plot plan drawing attached Pictures attached Township arborist's report (attach separate sheet if required)

Shade Tree Commission removal recommended yes / no

The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.











RADNOR TOWNSHIP SHADE TREE COMMISSION

Hazardous Tree Report

	Resident 1517 ASHTON LLC (Vince Sposato
	Address 312 West Ave
	Tree (Type, species, size, diameter at breast height) 1) Hem lock DRA 20" 2) Cedar DBA 13" 3) White Pine DBA 26" 4) Cedar DBA 10" 5) Cedar DBA 10" 6) Cedar DBA 12"
¥	Certified arborist's narrative report (attach separate sheet if required) SEF A+tached Sheet
	Certified arborist's name, address and # Michael Gillan (MG Tree) 701 Parkway Blub 13roomall PA 19008 PA Control 101 1317 PD - 220251
	PA Certified Arborist PD- 2205A
	Pictures attached <u>VCS</u> Plot plan drawing attached <u>VCS</u>
	Township arborist's report (attach separate sheet if required)

Shade Tree Commission removal recommended yes / no

The General Powers and Duties of the Shade Tree Commission section of the Ordinance (126.5 B) stipulates: In case of immediate necessity for the protection of life or property. Any shade or street tree described in this ordinance may be removed without first obtaining a permit, after inspection by a member(s) of the Shade Tree Commission or its designee.



July 9, 2015

Attention: Radnor Township Shade Tree Commission & Vince Sposato

<u>Project Location</u>

<u>312 West Ave.</u>

Radnor, Pa.

All trees listed above are growing within one to two feet to the foundation of the house. The root systems are pushing against the foundation causing cracks, allowing water to penetrate into the basement.

These trees have not been properly cared for by the previous owners, which have resulted in the trees declining and becoming unbalanced.

At this point trimming the trees would not be an option.

The largest of these trees is the White Pine . The White Pine tree has a substantial $18'' \times 30''$ rotted section approximately 25 feet up the trunk facing north towards West Avenue. This tree is in jeopardy of failing.

I would be available to meet at the property to point out all the defects of these hazardous trees.

Attached is a plot plan and pictures. All trees requesting to be removed are circled.



The thinking society of Arbitilities. Certified Arborist

Michael Gillan

Having successfully completed the requirements established by the Certification the above named is hereby recognized as an ISA Certified Arborists Board of the International Society of Arboriculture.

Afternational Society of Arboriculture Certification Board, Chair

International Society of Arboriculture

Executive Director

Fim Skiera

PD-2205A

Certificate Humber

Certified Since

Expiration Date

Dec 31, 2015

Oct 24, 2012



